

AD-A104 614

HORNER AND SHIFRIN INC ST LOUIS MO
NATIONAL DAM SAFETY PROGRAM, LAKE ST. LOUIS DAM (MO 10545) MISS-ETC(U)
MAY 78
DACW43-79-C-0047

F/8 13/13


UNCLASSIFIED

NL

for
AD0000



M



DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD A304614	(9)
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Lake St. Louis Dam (MO 10545), St. Charles County, Missouri,		5. TYPE OF REPORT & PERIOD COVERED Final Report.
6. AUTHOR(s) Horner & Shifrin, Inc.		6. PERFORMING ORG. REPORT NUMBER
7. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) DACW43-79-C-0047
9. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) (6) National Dam Safety Program. Lake St. Louis Dam (MO 10545) Mississippi River Basin, St. Charles County, Missouri. Phase I Inspection Report.		12. REPORT DATE May 1978
13. DI:		13. NUMBER OF PAGES Approximately 120
14. DI:		15. SECURITY CLASS. (of this report) UNCLASSIFIED
15. DI:		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DI: Approved for release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DTIC
ELECTE
SEP 28 1981

H


DD FORM 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

LAKE ST. LOUIS DAM
ST. CHARLES COUNTY, MISSOURI
MISSOURI INVENTORY NO. 10490

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

PREPARED BY:

HORNER & SHIFRIN, INC.
5200 OAKLAND AVENUE
ST. LOUIS, MISSOURI 63110

FOR:

U.S. ARMY ENGINEER DISTRICT, ST. LOUIS
CORPS OF ENGINEERS

MAY 1978

HS-7812



DEPARTMENT OF THE ARMY
ST. LOUIS DISTRICT, CORPS OF ENGINEERS
210 NORTH 12TH STREET
ST. LOUIS, MISSOURI 63101

IN REPLY REFER TO

SUBJECT: Lake St. Louis Phase I Dam Inspection Report

This report presents the results of field inspection and evaluation of the Lake St. Louis Dam. It was prepared under the National Program of Inspection of Non-Federal Dams.

SUBMITTED BY:

Paul R. Uheim
Chief, Engineering Division

15 June 78
Date

APPROVED BY:

Sam E. Muck
Colonel, CE, District Engineer

15 June 78
Date

Accession For	
NTIS GPA&I	<input checked="checked" type="checkbox"/>
DTIC T'S	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	<input type="checkbox"/>
By	
Distribution/	
Availability Co's	
Avail and/or	
Dist	Special
A 23	CP

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Lake Saint Louis
State Located: Missouri
County Located: St. Charles
Stream: Peruque Creek
Date of Inspections: 2 February 1978 and 22 March 1978

Based on a visual inspection and a review of performance history, the present general condition of the Lake Saint Louis dam and spillway is considered to be good. The following deficiencies were noticed during the inspection and are considered to have an adverse effect on the overall safety and future operation of the dam and spillway:

- a. Corrosion of the 72-inch steel drawdown pipe along with some loss of section due to flaking at the water line was observed. This condition is not considered serious at this time.
- b. The 72-inch drawdown pipe terminates at a point approximately in line with the downstream toe of the dam slope. There exists a possibility of erosion at the outlet during pipe discharge and the subsequent undermining of the dam.
- c. Erosion of the lakeside spillway outlet channel bank near station 12+90 was observed. This erosion is producing a concentration of flow at this point which could result in undermining of a portion of the spillway overflow section.
- d. Overflow of sewage at the wet well of the sewage lift station was noted at the time the downstream side of the dam was inspected.

There remains, until further investigations are made, some doubt as to the cause of the overflow. One of the reasons for the overflow occurring may be due to a surcharged condition which in turn may be due to excessive infiltration of the sewer line. It is important to verify if excess infiltration is occurring and that such is not the case immediately upstream or downstream or below the dam.


Based on evaluation of hydraulic-hydrologic data, it was found that the spillway outlet channel does not meet the criteria set forth in the guidelines for dam safety inspection work, furnished by the Department of the Army, office of the Chief of Engineers, for a dam of the size and hazard classification designated. The outlet channel, in order to satisfy the specified criteria, would be required to pass a flow of 86,000 cfs, which is equivalent to maximum probable flood (MPF). The spillway channel, as it is believed to presently exist, will pass a flow of 38,300 cfs. Spillway discharges of magnitudes greater than 38,300 cfs will result in a backwater condition developing over the spillway weir crest and a loss of spillway capacity due to weir submergence. Once submergence occurs the lake level will rise progressively until equilibrium of flow to the weir crest and channel outflow is reached, or until the dam is overtopped. The probability of a flood producing lake outflows of 38,300 cfs is believed to be greater than once in one thousand years.


A review of available data did not disclose that seepage and stability analyses of the dam were performed. Portions of the downstream toe of slope were found to be soft and wet. At the time of inspection it could not be concluded if this condition is due to seepage, ground thaw, surface runoff from snow and ice, or a combination thereof.

It was noticed during the inspection of the area in the vicinity of the dam that a number of liquid petroleum tanks have been installed immediately downstream from the Lake Sainte Louise Dam. The proximity of

these tanks to the Lake Saint Louis Dam presents a hazardous condition should failure of this dam occur. The owner is advised to investigate the safety of this dam and, if necessary, based on the results of this investigation, relocate the tanks.

It is recommended that the owner take the necessary action in the near future to correct or control the deficiencies reported herein.


Albert B. Becker, Jr.
P.E. Missouri E-9168


George K. Hasegawa
P.E. Missouri E-4551



OVERVIEW OF LAKE AND DAM

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
LAKE SAINT LOUIS DAM - ID NO. 10490

TABLE OF CONTENTS

<u>Paragraph No.</u>	<u>Title</u>	<u>Page No.</u>
SECTION 1 - PROJECT INFORMATION		
1.1	General	1
1.2	Description of Project	1
1.3	Pertinent Data	4
SECTION 2 - ENGINEERING DATA		
2.1	Design	6
2.2	Construction	7
2.3	Operation	8
2.4	Evaluation	8
SECTION 3 - VISUAL INSPECTION		
3.1	Findings	9
3.2	Evaluation	11
SECTION 4 - OPERATIONAL PROCEDURES		
4.1	Procedures	12
4.2	Maintenance of Dam	12
4.3	Maintenance of Spillway and Outlet Channel	12
4.4	Maintenance of Lake Drawdown Control Gate	12
4.5	Description of Warning System	13
4.6	Evaluation	13
SECTION 5 - HYDRAULIC/HYDROLOGIC		
5.1	Evaluation of Features	14
SECTION 6 - STRUCTURAL STABILITY		
6.1	Evaluation of Structural Stability	17

TABLE OF CONTENTS - Continued

<u>Paragraph No.</u>	<u>Title</u>	<u>Page No.</u>
SECTION 7 - ASSESSMENT/REMEDIAL MEASURES		
7.1	Dam Assessment	19
7.2	Remedial Measures	19

LIST OF PLATES AND CHARTS

<u>Plate No.</u>	<u>Title</u>
1	Regional Vicinity Map
2	General Plan of Dam and Spillway
3	Plan and Profile of Dam
4	Plan and Profile Steel Sheet Pile Cutoff
5	Profile Along 72" Steel Pipe
6	Details Gatewell Structure
7	Modifications to 6' Pipe
8	Dam Cross Sections
9	Dam Cross Sections
10	Site Plan of Spillway - Profile of Channel
11	Profile Overflow Spillway - Elevation Typ. Spillway End Wall
12	Overflow Spillway Sections and Details
13	Spillway Cross Sections
14	Boring Logs - May, June 1968
15	Sewage Lift Station and Wetwell
16	Lake Inflow - Outflow Hydrographs
17	Rating Curve - Spillway Outlet Channel

TABLE OF CONTENTS - Continued

<u>Chart No.</u>	
2-1 thru 2-13	Proposed Dam Site - Subsurface Investigations and Laboratory Analysis - May, June 1968 (Browning Testing Laboratories, Inc.)
2-14 thru 2-25	Drilling Report and Pressure Test Data - July 1969 (Test Drilling Service Co.)
2-26 thru 2-54	Core Drilling Report for Spillway Design - May, June 1970 and June, July 1971 (Test Drilling Service Co.)
2-55 thru 2-60	Geological Investigations and Reports, Missouri Geological Survey (21 Feb. 1963, 30 Sept. 1966, 6 June 1967, 12 May 1969)

APPENDIX

<u>Page No.</u>	<u>Title</u>
A-1 thru A-6	Construction Photographs
B-1 thru B-5	Inspection Photographs
C-1	Hydrologic Computations

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
LAKE SAINT LOUIS DAM - ID NO. 10490

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority. National Dam Inspection Act, Public Law 92-367, dated 8 August 1972.

b. Purpose of Inspection. The purpose of this inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam and spillway pose a hazard to human life or property.

c. Evaluation Criteria. This evaluation was performed in accordance with the "Phase I" investigation procedures as prescribed in "Recommended Guidelines for Safety Inspection of Dams" Appendix D, published by the Department of the Army, Office of the Chief of Engineers.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances. The Lake Saint Louis dam is an earthfill type dam rising approximately 47 feet above the original stream bed. Lake level is governed by a continuous concrete overflow type spillway approximately 810 feet in length with a side channel outlet. The spillway outlet channel is in rock cut to a point downstream from the dam where the channel transitions to the original drainage course of Peruque Creek. A 72-inch diameter steel pipe with a manually operated sluice gate serves the lake for drawdown purposes. Lake Saint Louis Blvd. traverses the dam crest crossing the side channel spillway at the west end of the dam. A general plan of the dam and spillway is shown on Plate 2.

b. Location. The dam and lake are located on Peruque Creek approximately 6 miles west of O'Fallon, Missouri, in St. Charles County, as shown on the map on Plate 1. The dam is located immediately upstream of the Interstate 70 crossing of Peruque Creek in Section 26, Township 47 North, Range 2 East.

c. Size Classification. The classification for size based on the height of the dam and storage capacity is categorized as intermediate. (Per Table 1, Recommended Guidelines for Safety Inspection of Dams, Appendix D.)

d. Hazard Classification. The Lake Saint Louis Dam has a high hazard potential, meaning that the dam is located where failure may cause more than a few lives lost, serious damage to homes, extensive agricultural, industrial and commercial facilities, important public utilities, main highways, or railroads. Further, the flood damage zone downstream of the dam was estimated to be ten miles. Within this damage zone are eight bridges, four of which are major bridges and includes Interstate Highway 70, three additional highways, and seven homes. Eleven additional homes may be subject to backwater flooding. The flood plain is extensively farmed.

e. Ownership. The dam is owned by the Lake Saint Louis Community Association, 20 Ellerman Road, Lake Saint Louis, Missouri, 63367. The association presently consists of 2,443 home and/or property owners.

f. Purpose of Dam. The dam impounds water for the purpose of recreation, for surrounding residential property owners, who are part of the Lake Saint Louis Community Association.

g. Design and Construction History.

(1) A hydrologic and hydraulic study of the proposed dam and lake was made in 1966 by the firm of Spence & Weinel, Inc., Consulting Engineers, St. Louis, Missouri, for the potential developers of the Lake Saint Louis subdivision property. This report recommended that the design of the dam and spillway be predicated on what the writers termed an Assumption A flood.

The flood for Assumption A is approximately equivalent to one-half the maximum probable flood (MPF). It was also stated in the Spence & Weinel report that if the MPF would not greatly increase the height of the dam it would be desirable to design the dam for this flood.

(2) The design of the dam and spillway was prepared during 1968 by Bernard G. Browning, P.E., Fulton, Missouri, for Lake Saint Louis Estates, Inc., which was then the site developer. Construction of the dam was started with the cut off trench excavated and fill approximately 20 feet in depth placed in the eastern portion of the dam. The 24-inch cast iron sanitary sewer pipe that runs down the center of the lake was installed across the dam site and the 72-inch steel drawdown pipe was also installed. Due to frequent flooding, the contractor was unable to place the impervious fill in the cut off trench in the vicinity of the Peruque Creek channel.

(3) In 1969, at the request of the ultimate developers, the Lake St. Louis Investment Corporation, Horner & Shifrin, Inc., Consulting Engineers, was engaged to review the design of the spillway and subsequently was authorized by the developers to redesign it. The spillway as designed by Horner & Shifrin, Inc., was based on the Assumption A flood.

(4) Horner & Shifrin, Inc. was also engaged to provide inspection services during the remaining construction of the dam and spillway. A steel sheet piling cut off was substituted for about 220 feet of the cut off trench in the vicinity of the creek channel and earth fill placed across the entire dam. The earth fill for the dam was essentially completed during the summer of 1970 with Horner & Shifrin, Inc. inspecting the placement and compaction of the fill. The overflow spillway and outlet channel were completed during the summer of 1973.

h. Normal Operational Procedure. The lake level is regulated by overflow of an uncontrolled spillway.

1.3 PERTINENT DATA

a. Drainage Areas. The areas tributary to the lake are primarily agricultural in use with a small amount of urban development. The watershed above the dam is approximately 17 miles long and the width varies to a maximum of about 5 miles. The total area is approximately 56.4 square miles (36,100 acres). The watershed area is outlined on Plate 1.

b. Discharge at Damsite.

- (1) Estimated known maximum flood at damsite ... 4,500 cfs
- (2) Overflow spillway capacity (including side outlet channel) ...
36,000 cfs
- (3) Gated 72-inch drawdown pipe capacity at normal pool elevation ...
700 cfs

c. Elevation (ft. above MSL).

- (1) Top of dam ... 512.0
- (2) Maximum pool-design surcharge ... 510.3⁽¹⁾
- (3) Normal pool ... 500.5
- (4) Spillway crest, normal pool section ... 500.5
- (5) Spillway crest, flood section ... 501.0
- (6) Streambed at centerline of dam ... 465.6
- (7) Maximum tailwater ... Unknown

d. Reservoir.

- (1) Length of maximum pool (elevation 510.3) ... 5.6 miles⁽¹⁾
- (2) Length of normal pool (elevation 500.5) ... 4.3 miles

e. Storage.

- (1) Normal pool ... 6,300 Ac.Ft.
- (2) Design surcharge (incremental) ... 6,900 Ac.Ft.
- (3) Top of dam (incremental) ... 1,450 Ac.Ft.

(1) For MPF assuming free discharge condition of outlet channel.

f. Reservoir Surface.

- (1) Top of dam ... 880 Acres
- (2) Maximum pool ... 830 Acres⁽¹⁾
- (3) Spillway crest ... 563 Acres
- (4) Normal pool ... 546 Acres

g. Dam.

- (1) Type ... Earthfill, homogenous
- (2) Length (approximate) ... 900 Ft.
- (3) Height ... 47 Ft.
- (4) Top Width ... 55 Ft.
- (5) Side Slopes
 - (a) Upstream ... 1v on 3h
 - (b) Downstream ... 1v on 2.5h
- (6) Cutoff ... Earthfill Trench/Sheet Piling
- (7) Slope Protection
 - (a) Upstream ... Rock rip-rap, dumped
 - (b) Downstream ... Grass

h. Spillway.

- (1) Type ... Concrete
- (2) Approximate length ... 810 Ft.
- (3) Crest elevation (feet above MSL)
 - (a) Normal pool section ... 500.5
 - (b) Flood section ... 501.0
- (4) Upstream Channel ... Lake
- (5) Downstream Side Channel
 - (a) Rock cut, approximate length ... 970 Ft.
 - (b) Bottom width ... 40 Ft. (min.), 70 Ft. (max.)

i. Outlet for Lake Drawdown.

- (1) Type ... Steel pipe, 72-inch diameter
- (2) Length ... 267 Ft.
- (3) Control ... Sluice gate, manually operated

(1) For MPF assuming free discharge condition of outlet channel.

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

a. Subsurface Investigations. Available test borings and other data for subsurface investigations for both the dam and spillway are included on Plate 14 and Charts 2-1 through 2-54. Geological investigations and reports prepared prior to the construction of the dam by the Missouri Geological Survey are included on Charts 2-55 through 2-60.

b. Dam. The dam was designed as a homogenous earthfill type embankment. The materials used, clays and silts, were obtained from nearby hillside and valley borrow areas. An impervious earthfill cutoff trench was designed to reduce the underseepage and prevent loss of water from the lake. A 72-inch diameter steel pipe with a manually operated control gate was provided for the purpose of unwatering the lake. Plans indicating the original design requirements of the dam are unavailable.

c. Spillway and Outlet Channel. The fixed crest spillway was designed as a concrete gravity section bearing on rock. The outlet channel was designed as a rock (limestone) cut section to a point about 400 feet downstream from the dam centerline to where the channel transitions to the original drainage course of Peruque Creek. The outlet channel has a bottom width varying from 40 feet at the upstream end to 70 feet at the downstream end. The channel side slopes in rock cut were specified to be 1 horizontal to 4 vertical. Details of the concrete gravity spillway as well as the side channel outlet are shown on the plans titled "Lake Saint Louis Main Dam," dated 17 July 1972, and are included as Plates 10 through 13. Due to flow in the spillway outlet channel, the elevation of the invert based on survey was not obtained. However, it is believed that the channel was not excavated to the full depth shown in the plans but that the invert near the downstream end is about 4.5 feet higher than specified.

2.2 CONSTRUCTION

a. Dam. At the time Horner & Shifrin was engaged by the Lake St. Louis Investment Corporation, the earthfill dam, including cutoff trench, had been under construction for some time. Approximately 20 feet of fill was in place near the east abutment. The 72-inch drawdown pipe as well as the 24-inch sanitary sewer pipe had also been installed beneath the main body of the dam. However, due to flooding of the excavation, the contractor had been unable to place the impervious fill for the cutoff trench in the vicinity of the old creek channel.

Under the surveillance of Horner & Shifrin, a steel sheet piling cutoff was substituted for the earthfill trench section from station 19+14 to station 21+31 in order to proceed with construction of the dam. Placement of the remaining fill was monitored and the compaction effort recorded. The 72-inch drawdown pipe was extended some 34 feet to a point just beyond the downstream toe of slope, a headwall was constructed on the upstream end of the 72-inch pipe, and construction of the gatewell structure was completed.

Plans for modifying the 72-inch pipe, including construction of the gatewell and upstream headwall, as well as cross-sections used to complete construction of the dam are shown on Plates 3 through 9. Photographs of the dam taken during construction are included on Page A-1 of the Appendix.

b. Spillway and Outlet Channel. Construction of the concrete spillway section was accomplished according to plan with the exception of the reach between stations 4+60 and 6+38. Due to poor rock foundation conditions, as indicated by the test borings, it was planned to construct an earthfill embankment section in this area. When excavation of the overburden in this area revealed that the foundation rock could be satisfactorily utilized, and at the request of the developer, it was decided to extend the concrete overflow section through this reach and eliminate the earthfill embankment. Considerable effort was expended removing badly weathered rock, cleaning the earth

filled cavernous rock areas, and filling with concrete the resulting voids within the limits of the overflow section in order to attain a sound, impervious foundation. Photographs taken during construction showing an area of the cavernous rock foundation that has been prepared for filling with concrete, as well as other photographs taken during construction of the spillway overflow section, are included on Pages A-2 through A-5 of the Appendix.

The outlet channel was excavated in limestone by drilling and blasting. Side slopes were maintained at 4 vertical to 1 horizontal. The alignment of the channel was maintained essentially as planned, however it is believed that the invert was constructed higher than the profile grades specified. No evidence of faulting of the bedrock during excavation of the channel was noted.

2.3. OPERATION

Lake level is governed by overflow of the uncontrolled spillway. The gate on the 72-inch outlet pipe is maintained closed and used only for lake drawdown purposes.

2.4 EVALUATION

a. Availability. Engineering data available for assessment of the spillway and outlet channel design was substantial. The data available for assessment of the design of the dam was found lacking with regard to the soil strengths of the foundation and embankment.

b. Adequacy. Since soil strength data is unavailable to make a complete assessment of the design of the dam, it is recommended that the owner engage a qualified engineer to obtain the necessary soil test data and to perform detailed stability and seepage analyses.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

a. General. A visual inspection of the dam, spillway, outlet channel, the outlet end of the drawdown pipe, and other related features was made by Horner & Shifrin engineering personnel on 2 February 1978 and 22 March 1978. Also inspected was the Highway 40-61 Bridge crossing Peruque Creek at the upstream end of the lake and the various bridges crossing Peruque Creek from the dam downstream to Highway 79. Below Highway 79 the stream emerges onto the flood plain of the Mississippi River and is considered to be the downstream limits subject to damage by flooding should failure of the dam occur. Photographs of the dam, spillway, and the Highway 40-61 Bridges are included on Pages B-1 through B-6 of the Appendix.

b. Dam. The upstream and downstream slopes of the dam were found to be in good condition except for some erosion, caused by surface storm runoff, of the downstream slope where the dam joins the east abutment and of the upstream slope at the east abutment of the Lake Saint Louis Boulevard Bridge.

The downstream toe of slope was found to be soft and wet in several areas. At this time of the year, it cannot be concluded if this condition is due to seepage, ground thaw, surface runoff, or a combination of all the aforementioned.

The downstream flood plain adjacent to the dam was also noticeably wet, with ponded water appearing in several locations, however this condition can be attributed to poor drainage of surface runoff and to overflow of the sewage lift station wetwell. Details of the sewage lift station and wetwell are shown on Plate 15.

c. Drawdown Pipe. The 72-inch uncoated steel pipe provided for unwatering the lake was rusted and showed signs of corrosion at the water line.

Water could be heard entering the upstream end of the pipe, presumably due to leakage about the control gate. A minor quantity of water was noticed flowing from the pipe. Since, at this time, the pipe was two-thirds full of backwater caused by downstream channel obstruction, an internal inspection of the pipe from the outlet to the gate was not undertaken. The exposed elements of the gate operator and gatewell structure appeared to be in good condition.

d. Spillway and Outlet Channel. The fixed crest concrete spillway section appeared to be in good condition. No deterioration of the concrete due to weathering or damage from ice was observed. Leakage at the vertical joints between adjacent sections was not appreciable. A significant amount of erosion of the left bank of the outlet channel between the overflow section and the channel has occurred in the vicinity of channel station 12+40. The erosion is the result of the washing out of the soil fill in the existing solution channel in the limestone bedrock on which the spillway is constructed. A picture of the erosion of the solution channel is shown on Photograph No. 8 of the appendix. At the time of construction of the spillway, the portion of the solution channel occurring below the spillway was thoroughly cleaned of earth and backfilled with concrete. The erosion has partially exposed the concrete fill. The solution channel is about 20 feet wide at the top and is estimated to be about 40 feet in length. It appeared that the erosion has nearly stabilized and that erosion from this time on would be due to weathering of the exposed rock surfaces. Loss of the bank is causing spillway discharge to concentrate at this location. Additional erosion of the bank was noticed along the east side of the paved chute downstream from the normal pool control section. The outlet channel banks, with the exception of the loss of section in the vicinity of station 12+40, were found to be in good condition and maintaining their slopes. Some areas of the channel bottom did have an accumulation of large stones and boulders, apparently due to sloughing of loose rock along the upper regions of the right bank.

e. Highway 40-61 Bridges. The Highway 40-61 Bridges at the upstream end of the lake were visually examined during the inspection of 22 March 1978. No

noticeable adverse effects due to the presence of the lake were detected. The lake at the time of the inspection was approximately 6 inches above normal pool level at the spillway.

f. Downstream Channel. The Peruque Creek channel downstream from the dam is unimproved. The flood plain between the dam and the Highway 79 Bridge, approximately 9 miles downstream, varies in section with the average width being approximately 1,500 feet. The narrowest section, approximately 600 feet in width, occurs at a point approximately 1 mile upstream from the Highway 79 Bridge or roughly 8 miles downstream from the dam. The stream is crossed, beginning at the dam and proceeding downstream by the I-70 South Outer Road Bridge, the I-70 East Bound and West Bound Bridges, the North Outer Road Bridge, the Norfolk & Western Railroad Bridge, Hoff Road Bridge, County Route P Bridge, a private road bridge, County Route M Bridge, and State Highway 79 Bridge. The flood plain is principally farm land; however, it is being developed in some areas with several homes completed and occupied. In addition, primarily along Route M, there are several older residences that lie within the flood plain limits.

3.2 EVALUATION

Deficiencies observed during this inspection and noted herein are not considered significant or of serious potential to warrant immediate remedial action.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES

Since the spillway is uncontrolled and the lake drawdown pipe is maintained closed, there are no gated facilities for controlling lake discharge.

4.2 MAINTENANCE OF DAM

A visual inspection of the dam and spillway is normally performed by personnel of the Lakes and Parks Department, Lake Saint Louis Community Association, on a monthly basis. This inspection is done on foot and includes examination of the dam slopes, the area immediately downstream from the dam, the gate structure, the spillway, and the spillway outlet channel. The grass on the dam slopes and downstream berm is mowed on a regular basis. Shrubs and trees are not permitted in these areas. Animal burrows are filled when noticed. No records are kept of these inspections or maintenance performed.

4.3 MAINTENANCE OF SPILLWAY AND OUTLET CHANNEL

To date, it would appear that little maintenance work has been performed in the spillway area as is evident by the erosion of the channel bank in the vicinity of station 12+40 and the accumulation of boulders and large rocks in the outlet channel.

4.4 MAINTENANCE OF LAKE DRAWDOWN CONTROL GATE

The gate on the 72-inch drawdown pipe is the only mechanical item capable of being operated. It has been reported by the Director of the Lakes and

Parks Department that the gate is in operating condition although it leaks moderately in the closed position. The gate operator was well lubricated and appeared to be in good condition.

4.5 DESCRIPTION OF WARNING SYSTEM

There presently is no warning system in effect in case of extreme high water or sudden failure of the dam. With a county maintained road traversing the dam crest and a bridge crossing the spillway outlet channel, there is rather frequent observation of the lake conditions and the overflow of the spillway by many interested residents of the area. Due to the presence of a large number of people in the dam vicinity, it is likely that adequate warning of overtopping of the dam would be given if such a condition was developing.

4.6 EVALUATION

The presence of full-time employees under responsible supervision, as is the case at Lake Saint Louis, to maintain and inspect the dam, is considered beneficial to the safety of the dam. It is recommended that maintenance on a regular basis of the spillway outlet channel be included along with the other normally maintained features. The owner should determine if ponded water on the berm immediately below the dam is due to overflow of the wetwell. Saturation of the berm due to poor drainage is undesirable since it has an adverse effect on the stability of the dam. The owner should provide positive means for draining surface runoff in this area.

In order to insure proper operation of the sluice gate on the lake draw-down pipe, the gate should be periodically opened fully and closed.

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

a. Design Data. The hydraulic and hydrologic data for the design of the dam and spillway is available. Beginning with the 1966 study by Spence and Weinel and continuing with the investigations by Horner & Shifrin for the design of the spillway, it was concluded that the hydraulics of the spillway and the hydrology of the lake and upstream tributary area have been sufficiently investigated. Data used for hydrologic computations is presented on Page C-1 of the Appendix.

The design of the spillway and outlet channel was based on the Assumption A flood which is approximately equivalent to one-half of the maximum probable flood (MPF). Under the Assumption A flood, the peak inflow to the lake amounts to 44,800 cfs, while for MPF the peak inflow amounts to 90,500 cfs. For a storm with a frequency of once in 300 years the peak inflow to the lake would be 13,600 cfs, and for a frequency of once in 100 years the peak inflow amounts to 10,700 cfs. Hydrographs for lake inflow and outflow for PMF, Assumption A, and 300 year storm are presented on Plate 16. Lake outflow is based on spillway crest length believed to have been constructed.

The limiting factor governing the level of the lake, based on hydraulic investigations, was found to be the capacity of the spillway outlet channel. It is believed that the channel invert was not constructed to the plan elevations specified on the construction drawings prepared by Horner & Shifrin in 1972 but is approximately 4.5 feet higher. Based on the channel invert believed to presently exist, the capacity of the outlet channel was found to be 33,500 cfs without exceeding elevation 508.0 in the lake. Elevation 508.0 was considered to be the maximum lake surface elevation desirable for development of the property about the lake and therefore to be used for spillway design.

A second and smaller lake, Lake Sainte Louise, is located immediately to the west and north of Lake Saint Louis. Its location is shown on Plate 1. The main stem of the lake is roughly parallel to Lake Saint Louis and lies about 2,000 feet south of I-70 highway. The spillway for this lake discharges to an arm of Lake Saint Louis at a point approximately 7,000 feet from the main dam. An earthfill type dam, approximately 50 feet high, serves to impound water for Lake Sainte Louise. The dam lies near the upper end of the aforementioned arm of Lake Saint Louis and any discharges from Lake Sainte Louise due to the failure of the dam would be into a relatively shallow section of Lake Saint Louis and at a point where the lake is not very wide. Based on data obtained from U.S.G.S. topographic maps, the approximate surface area of Lake Sainte Louise is 75 acres and the storage volume at normal pool level is 1,070 acre-feet. The tsunami or tidal wave effect on Lake Saint Louis, should sudden failure of the Lake Sainte Louise dam occur, has not been considered in these investigations. However, failure of the dam will undoubtedly cause considerable damage to much of the development around the arm of Lake Saint Louis immediately downstream from the Lake Sainte Louise dam. Therefore, a Phase I inspection of Lake Sainte Louise is warranted.

b. Experience Data. Since completion of the spillway in September of 1973, the maximum depth of flow over the spillway weir, according to observations made by individuals at Lake Saint Louis, is believed to be 12 to 18 inches. Using a conventional formula for a broad-crested weir, a depth of 18 inches amounts to a flow of about 4,500 cfs.

c. Visual Observations. It was noticed in areas downstream from the dam that relatively low spillway discharges will force the stream out of its natural channel. This, however, is not a new condition or one that has developed since construction of the dam. Estimates of discharge that will be contained within the natural channel vary, but it is believed that flows as low as 1,500 cfs will cause the stream to flood in some areas.

d. Overtopping Potential. The potential for overtopping the dam is believed to be relatively low if the outlet channel can allow flow to discharge

at the rate required. This rate was found to be 33,500 cfs for a lake surface elevation of 508.0, and 38,300 cfs for a lake surface elevation of 512.0 (top of dam). Once the outlet channel capacity is reached, a back-water condition will develop, and additional increases in spillway discharge will result in higher lake levels. The MPF outflow, 86,000 cfs, so greatly exceeds the capacity of the spillway outlet channel that, for a flow of MPF magnitude, it is believed that the dam will be overtopped. A rating curve for the spillway outlet channel indicating the relationship of channel capacity to lake level is presented on Plate 17.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations. No evidence of instability of the dam or overflow spillway was noticed during the visual inspection of March 22, 1978. No mention of slides or other signs of instability were reported by the owner.

b. Design and Construction Data. Stability analyses of the dam section and soil shear strengths based on field or laboratory testing are not available for review. A review of the field compaction tests, obtained during placement of the rolled earth fill for the dam, indicated that for a total of 37 tests taken, 5 exceeded 95 percent of maximum dry density at optimum moisture content, per ASTM D-698, and that the average of all tests made was 92.6 percent.

Overturning and sliding stability were investigated during design of the concrete spillway overflow section in accordance with the procedures outlined in Chapter VII of the technical publication "Design of Small Dams" by the Bureau of Reclamation, U.S. Department of the Interior. The 28 day strength of the concrete was assumed to be 3,000 psi and a minimum of 6 sacks of cement per cubic yard of mix was specified. Of 25 test cylinders obtained during construction, the minimum compressive strength of the concrete cylinders tested was found to be 3,519 psi.

c. Operating Records. The dam and spillway have not been monitored in any form during the post construction period. No records have been kept of lake level, spillway discharge, dam settlement, or seepage during this time.

d. Post Construction Changes. Since completion of the dam in 1970 and the spillway in 1973, there have been no changes to these improvements.

e. Seismic Stability. Seismic forces were not considered in the design of the spillway. Since the lake is located within a Zone II seismic probability area, an earthquake of the magnitude predicted is not expected to produce a hazardous condition to the dam or spillway.

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1 DAM ASSESSMENT

a. Safety. Based on the present condition of the dam, the physical proportions of the dam, such as the width of the crest (55 ft.) and side slope ratios (1v on 3h upstream, 1v on 2.5h downstream), knowledge of materials placed and methods used during construction, and history of performance, the dam is believed to be capable of withstanding various normal combinations of earth and water forces applied. This capability does not, however, preclude the potential for overtopping of the dam due to storms greater than one-half maximum probable flood magnitude.

b. Adequacy of Information. Soil strength data and properties necessary to assess the overall stability of the dam were unavailable for review.

c. Urgency. The remedial measures recommended herein are not considered to be of imminent necessity. It is recommended, however, that implementation of the actions recommended in paragraph 7-2 be undertaken in the near future.

d. Necessity for Phase II. Based on the findings and assessment of the safety of the dam developed during this investigation, a Phase II study is not recommended.

e. Seismic Stability. Since the dam is located in a Zone II seismic design area, an earthquake of the predicted magnitude is not expected to be hazardous to the dam.

7.2 REMEDIAL MEASURES

a. Alternatives.

(1) The spillway side outlet channel should be enlarged in order to increase its capacity for storm runoff of maximum probable flood (MPF) magnitude.

Hydraulically the overflow spillway and dam are considered to be adequate for MPF requirements.

(2) Obtain the necessary soil data and perform seepage and stability analyses to assess the stability of the dam for conditions which the dam has not experienced. The analysis should include the necessary investigations to determine the need for a sub-drain with a filter system and other drainage devices to prevent toe softening downstream of the dam proper. In addition, investigations should be made to determine if the ponding of water on the berm downstream from the dam is due entirely or in part to overflow of the sewage lift station. Positive drainage of surface runoff in this area should be provided.

(3) A number, approximately 60, of liquid petroleum (LP) tanks are located in an area immediately downstream from the Lake Sainte Louis Dam. These tanks are serviced by O'Fallon Gas Service, Inc., and provide gas for heating of many homes and condominiums within the Lake Saint Louis development. It was calculated that if the entire volume of water in Lake Sainte Louise was allowed to discharge into Lake Saint Louis, the rise in the level of Lake Saint Louis would be on the order of 2 feet. This rise above normal pool level of Lake Saint Louis would not cause any serious damages. However, if failure of the Lake Sainte Louise dam should occur in such a way that a large volume of water would be released suddenly, the mass of water could create a wave of such magnitude that serious damage not only to the LP tank farm but also to the development about the edge of the lower lake would undoubtedly occur. It, therefore, is believed that a very hazardous condition exists and a Phase I investigation of the Lake Sainte Louise Dam is recommended.

(4) Perusal of the available records of the construction of the 24-inch sanitary sewer under the dam did not uncover sufficient information to verify the type of material or type of joints and class of pipe used. Although drawings available showed anti-seep collars were to be constructed on the sanitary sewer, verification of the fact that this was done was not possible at this time. As far as it was determined, there appears no provision on the upstream

side of the dam to isolate the sanitary sewer should failure or other problem occur in the sanitary sewer under the dam.

Due to backwater in the 72-inch lake drawdown pipe at the time of the inspection, visual examination of the interior of the pipe was not made except near its outlet. It was noted at the outlet that a considerable amount of flaking of the interior surface near the water line had occurred. Drawings which were obtained indicated that seep collars were to be constructed on the pipe under the dam. Verification of the actual construction of these collars could not be made. Since these uncertainties occur, further investigation of the structural condition should be made of both pipe lines under the dam as well as the determination of the presence or absence of the seep collars.

b. O & M Maintenance and Procedures.

(1) The 72-inch diameter uncoated steel lake drawdown pipe should be lined or protected by some other means to eliminate the concern of its failure due to loss of section from corrosion on both the inside and outside surfaces.

(2) The lake drawdown pipe should be extended to avoid scour of foundation soils at the existing discharge location and possible undermining of the dam.

(3) If the results of the recommended stability and underseepage analyses so indicate, a subdrain with filter system should be installed in line with and approximately at the location of the downstream toe of slope of the dam. The subdrain system should have an outlet that cannot be contaminated by backflow.



(4) The partially eroded bank of the spillway outlet channel at about station 12+40 should be restored. The overflow spillway foundation should be carefully examined for undercutting when this work is performed and any voids or openings discovered should also be restored.

(5) The eroded area on the east side of the spillway chute for the normal pool control section should be repaired so as to prevent additional erosion of the bank and undercutting of the bay and channel bottom.

(6) The eroded earthen areas of the upstream and downstream faces of the dam should be restored and protected.

(7) The manually operated control gate on the 72-inch lake drawdown pipe should be operated to ensure proper function. At present, this gate leaks moderately, and unless for some reason the leak increases severely, should not impair the performance of the lake from a recreational standpoint.

(8) It is recommended that the lake owners association continue to employ qualified personnel for the purpose of operating and maintaining the dam, spillway, and appurtenant features. Inspection of the dam and spillway should be continued, as at present, on a monthly basis. Records indicating the date of the inspection, the items inspected and their condition, the urgency of any action to be taken in the case where remedial work is deemed necessary, and any additional information considered pertinent should also be included. The names of personnel performing the inspection, should also be a matter of record. A copy of this inspection report should be submitted without delay to the lake owners association for further consideration. It is also recommended, for future reference, that records be kept of all inspections, maintenance work, remedial measures, and improvements.



LOCATION MAP


WATERSHED BOUNDARY


HICKORY CREEK

CALAWAY

DRY CREEK

8





REGIONAL VICINITY MAP

4


(WESTBOUND LANES)

I-70


(EASTBOUND LANES)

I-70

(SOUTH OUTER ROAD)




LAKE SAI




GENERAL PLAN OF DAM AND SPILLWAY

PLAN	
NOTE BOOK	NO.




ANTI-SEEP




PLAN VIEW OF ANTI-SEEPS

PROFILE	
NOTE BOOK	NO.







PLAN VIEW OF DAM AREA



PLAN AND PROFILE
OF DAM
PREPARED BY
LAKE SAINT LOUIS
JUNE 17, 1968





PROFILE



LAKE SAINT LOUIS
INC.



1065

Date July 22, 1965




PREPARED BY
LAKE SAINT LOUIS
AUG. 6, 1965
PROJECT BY MORRIS & SMITH, INC.
AUG. 22, 1965
SCALE 1" = 10'


••



DETAILS OF INTAKE ON EXP
SCALE 1/4" = 1'




SECTION A-A
SCALE 3/8"=1'-0"



SECTION B-B
SCALE 3/8"=1'-0"

NOTE: ALL BARS ARE 1/2" DIA.
 12" LONG UNLESS OTHERWISE NOTED
 SPACING MINUS 1/2" FROM FACE
 ALL BARS ARE GALVANIZED AFTER
 FABRICATION




PLAN OF TOP SLAB
 SCALE 3/8" = 1'-0"


BAR SCHEDULE

MARK	SIZE	QTY	LENGTH	TYPE	C	B	D
A1	6	10	17	12-8	3-9	3-0	
A2	4	42	17	11-11	1-8		
A3	4	42	11				
A4	6	18	12-8				
A5	4	60	2-2				
A6	6	6	7-0				
A7	4	60	10-2				
A8	4	60	11-2				
A9	4	60	6-10				
A10	6	52	5-8				
A11	4	36	10-8				
A12	4	34	10-8				
A13	5	16	6-10				
A14	4	17	3-16	17	1-0	2-6	
A15	4	4	10-6				
A16	4	17	4-5				
A17	6	52	18-2	17	10-8	3-9	3-9


NOTE: TYPE 1 BARS ARE STRAIGHT BARS




1/2" BAR




TYPE 17



TYPICAL SHAFT SECTIONS
 SCALE 3/8" = 1'-0"





DETAIL OF GRATE CLAMP
 & ANGLE SEAT
 SCALE 3" = 1'-0"



GRATE HINGE
 SCALE 3/8" = 1'-0"

3/15/69	BAR SCHEDULE REVISION A5, A11, A13	D.C.L.
REV. DATE	DESCRIPTION	BY
LAKE ST. LOUIS INVESTMENT CORPORATION		
LAKE ST. LOUIS		
MAIN DAM		
DETAILS-GATEWELL STRUCTURE		
SCALE AS SHOWN	HORNE & SHIFRIN, INC.	DATE SEPT 1968
DESIGNED BY J.B.B.	CONSULTING ENGINEERS	DRAWING
DRAWN BY D.C.L.	ST. LOUIS, MISSOURI	SHEET NUMBER
CHECKED BY D.C.L.		TOTAL SHEETS
NO. 9942		2 3



DAM & ROADWAY

C.

CLAYS & SILTS

EXIST GROUND

FRANKLIN FILL

2' MIN. CRUSHED STONE

EXIST 6" DIA. STEEL PIPE

EXIST 6" DIA. STEEL PIPE


EXIST 6" DIA. STEEL PIPE

RECONNECT BEVELLED END SECTION AT THIS LOCATION.

QUARRY & DUMPS STONE RIBBON

SECTION A-A
SCALE 1"=10'

CUT END OF PIPE AND GRIND AS REQUIRED TO 30° BEVEL PROVIDE DOUBLE BEVEL WELD FULL PENETRATION.



CLAY & SILT DUMPS
STONE RIBBON

SECTION C-C
SCALE 1"=10'



LAKE SAINT LOUIS INVESTMENT CORPORATION
**LAKE ST. LOUIS
MAIN DAM**
MODIFICATION TO 6" PIPE OUTLET

SCALE AS NOTED
DESIGNED
DRAWN BY
CHECKED BY
HS NO. 8842

HORNER & SHIFRIN, INC.
CONSULTING ENGINEERS
ST. LOUIS, MISSOURI

DATE JUNE, 1970
DRAWING SHEET TOTAL
NUMBER SHEETS
24 29

PLATE

520

510

500

490

480

470

460

520

510

500

490

480

470

460

520

510

500

490

480

470

UPSTREAM

FINISHED GRADE

STONE RIPRAP &
GRANULAR BEDDING

COFFERDAM

FINISHED GRADE

COMPACT FILL WITH
HAND OPERATED
TAMMERS

STEEL SHEET
PIILING

2.10.120




FINISHED GRADE


STONE RIPRAP &
GRANULAR BEDDING


COFFERDAM

EXCAVATE AND
BACKFILL WITH
CLAYS AND SILTS
FROM BORROW AREA

COMPACT WITH HAND
OPERATED TAMPING
EQUIPMENT









CURVE ①
 $\Delta = 49^\circ 25' 00''$
 $R = 85.00'$
 $T = 39.11'$
 $L = 73.31'$

CURVE ②
 $\Delta = 27^\circ 27' 20''$
 $R = 152.88'$
 $T = 37.34'$
 $L = 73.26'$


CURVE ③
 $\Delta = 66^\circ 11' 10''$
 $R = 78.00'$
 $T = 75.57'$
 $L = 120.05'$



SITE PLAN OF SPILLWAY



PROFILE OF SPILLWAY CHANNEL
 SCALE: 1"=20' VERT. 1"=50' HORIZ.



GENERAL NOTES

A. GENERAL


1. Excavation for 12-inch minimum embedment of spillway base and embankment cutoff trench in sound limestone rock shall be performed such that adjacent rock remains intact and undisturbed.
2. Impervious fill shall be clays and/or silty clays obtained from hillside borrow areas approved by the Engineer.
3. Impervious fill shall be compacted in 8-inch maximum lifts unless otherwise specified to 95 per cent maximum density at optimum moisture content per ASTM Test D-698, "Standard Proctor Method."
4. All fill placed within 2 feet of spillway walls or base sections shall be mechanically compacted in 6-inch maximum lifts to 95 per cent maximum density per ASTM D-698. Backfill shall be uniformly and symmetrically placed.
5. Spillway monoliths and end tie-in sections shall be placed in alternate sections with a minimum elapsed period of 120 hours between placement of adjacent sections.
6. Riprap shall be sound durable quarry-run limestone with a maximum size of 250 lbs.
7. Bedding shall be well-graded sound durable limestone with a maximum size of 3 inches.
8. Surfacing shall be crushed limestone similar to bedding.

B. CONCRETE

1. All detailing, fabrication, and placing of reinforcing bars shall comply with the ACI "Manual of Standard Practice for Detailing for Reinforced Concrete Structures," ACI-315.
2. All concrete shall have a minimum compressive strength in 28 days of 3,000 psi; shall contain a minimum of 6 sacks of Type II, ASTM C-150 portland cement per cubic yard, and shall not contain more than 5.25 gallons of water (total moisture) per sack of cement. An air-entraining agent, conforming to the requirements of ASTM C-260 shall also be included in the mix. The maximum allowable slump for base sections shall be 2 inches and for walls, 3 inches. Concrete aggregates shall conform to ASTM C-33. Coarse aggregate shall be well graded crushed limestone with a maximum size of 1-1/2 inches. The mix shall be approved by the Engineer prior to construction.
3. All exposed concrete shall be cured with wet burlap coverings for a period of not less than 120 hours. Forms in contact with the concrete shall be kept wet for a period of not less than 120 hours. If forms are removed during the curing period the exposed concrete surface shall be cured, as specified above, for the balance of the curing period. In lieu of moist curing, all concrete may be membrane cured using "Mornure 40W" (white) curing compound applied at a coverage rate of 200 sq. ft. per gallon.
4. Reinforcing bars, including anchors, shall conform to ASTM A-615, Grade 60.
5. Reinforcing bars shall have a clear concrete cover of 2 inches unless otherwise shown on the drawings.
6. Waterstops shall be 6 inches wide by 3/8 inch thick, 2 bulb type PVC waterstops, manufactured in accordance with CRD-C572.
7. All exposed edges of concrete walls shall have a 3/4-inch chamfer. The upstream and downstream corners of the overflow spillway crest shall be rounded to a 3-inch radius.
8. All exposed unformed concrete surfaces shall have a wood float finish.

NOTES:

1. TEST BORINGS B-4 THRU B-18 DRILLED MAY & JUNE, 1970.
2. TEST BORINGS B-101 THRU B-117 DRILLED JUNE & JULY, 1971




* ITEM NOT CONSTRUCTED.




REV.	DATE	DESCRIPTION
LAKE SAINT LOUIS INVESTMENT CORPORATION		
LAKE SAINT LOUIS		
MAIN DAM		
SITE PLAN OF SPILLWAY		
PROFILE OF CHANNEL		
SCALE: 1" = 50'	DESIGNED BY A.B.D.	HORNER & SHIFRIN, INC. CONSULTING ENGINEERS ST. LOUIS, MISSOURI
DRAWN BY E.L.H.	CHECKED BY D.C.L.	
NS NO 72.48		
DATE: 11/17/71		DRAWN BY: []
SHEET NUMBER: 1		OF: 1

2 PLA





Scale: 1" = 20'




ELEVATION TYPICAL SPILLWAY END WALL AT EM

Scale: 1" = 5'




W SPILLWAY




- NOTES:
1. CONSTRUCT END WALL TIE-IN AT MAIN DAM SIMILAR TO THAT SHOWN FOR END WALL TIE-IN AT EMBANKMENT. PROVIDE CONSTRUCTION JOINT AT MID-POINT OF WALL LONGITUDINAL REINF. TO EXTEND THRU JOINT.
 2. END WALL TIE-IN SECTION AT EMBANKMENT TO FOLLOW E ALIGNMENT OR MAY BE CONSTRUCTED IN CHORDS NOT EXCEEDING 1'-0" IN LENGTH.
 3. OVERFLOW SPILLWAY END ABUTMENT TO KEY 1'-0" MIN INTO SOUND ROCK.

* ITEM NOT CONSTRUCTED


D WALL AT EMBANKMENT



REV.	DATE	DESCRIPTION	BY
LAKE SAINT LOUIS INVESTMENT CORPORATION			
LAKE SAINT LOUIS MAIN DAM			
PROFILE OVERFLOW SPILLWAY ELEVATION TYP. SPILLWAY END WALL			
SCALE AS SHOWN		DATE JULY 17, 1972	
DESIGNED BY: A.B.B.		DRAWING	
DRAWN BY: D.C.E.		SHEET NUMBER	
CHECKED BY: D.C.E.		TOTAL SHEETS	
WS NO. 1248		2 4	
HORNER & SHIFRIN, INC.		ST. LOUIS, MISSOURI	



TYPICAL OVERFLOW SECTION




TYPICAL END TIE-IN SECTION

DETAILS OF MINIMUM GRAVITY SPILLWAY SECTIONS


Scale: 1/4" = 1'-0"

SPECIAL NOTE

DIMENSIONS MARKED WITH ASTERISK(*) ARE VARIABLE AND DEPEND ON ELEVATIONS OF SOUND ROCK. HOWEVER THESE DIMENSIONS ARE MINIMUM FOR BOTH THE GRAVITY AND NON-GRAVITY SECTIONS SHOWN



TYPICAL OVERFLOW SECTION




TYPICAL END TIE-IN SECTION

DETAILS OF MINIMUM NON-GRAVITY SPILLWAY SECTIONS


Scale: 1/4" = 1'-0"

NOTES:
1. #5 BARS TO BE CONTINUOUS THRU CONSTRUCTION JOINTS WITH 15" LAP SPLICES, STAGGERED, AT ANCHOR LOCATIONS



TYPICAL ANCHOR LOCATION PLAN


NOTES:
1. GROUT #8 ANCHOR IN 3" HOLE W/ 1" DIA. #4 BARS USING A THICK PASTE CONSISTENCY
2. HOLES TO BE DRILLED WITH A ROLLER BIT AND FLUSHED CLEAN PRIOR TO GROUTING



TYPICAL DETAIL NOTCH CURB

Scale: 1/4" = 1'-0"

PAGE
LAKESIDE




TYPICAL SECTION AT NOTCH


NOTES

1. COVER END OF DRAIN PIPE WITH #4 HARDWARE CLOTH AND SECURE SLOPE PIPE TO DRAIN
2. FILTER MATERIAL TO CONSIST OF 3/4" UNIFORM SIZE CRUSHED ROCK

505



TYPICAL SECTION AT NOTCH




3-6-6 @ 120°
SECURE ABOUT
ANCHOR 2 SETS
PER ANCHOR REQ.
ONE SET TOP & ONE
SET BOTTOM OF HOLE

GROUT 18 REIN BAR ANCHOR

PLAN-ANCHOR HOLE & BAR SETTING
DETAIL A

Scale: Half-Size

Scale: Half-Size








TYPICAL CONST. JOINT DETAILS

No Scale





REV. DATE	DESCRIPTION
<p>LAKE SAINT LOUIS INVESTMENT CORPORATION</p> <p>LAKE SAINT LOUIS MAIN DAM</p> <p>OVERFLOW SPILLWAY SECTIONS AND DETAILS</p>	
<p>SCALE AS NOTED</p> <p>DESIGNED BY: A. B. S.</p> <p>DRAWN BY: D. E. E.</p> <p>CHECKED BY: J. D.</p> <p>NS NO 7248</p>	<p>HORNER & SHIFRIN, INC.</p> <p>CONSULTING ENGINEERS</p> <p>ST. LOUIS, MISSOURI</p>
	<p>DATE JULY 15, 1964</p> <p>DRAWING</p> <p>SHEET NUMBER</p> <p>3</p>







ITEM NOT CONSTRUCTED



A-B-B Channel Flowline Corrected REV DATE DESCRIPTION BY	
LAKE SAINT LOUIS INVESTMENT CORPORATION LAKE SAINT LOUIS MAIN DAM SPILLWAY CROSS SECTIONS	
SCALE 1"=10' DESIGNED BY A.B.B. DRAWN BY H.E.W. CHECKED BY D.C.L. HS NO 1248	DATE JULY 17, 1978 HORNER & SHIFRIN, INC. CONSULTING ENGINEERS ST LOUIS, MISSOURI
DRAWING SHEET NUMBER 4	TOTAL SHEETS 4






LAKE SAINT LOUIS MAIN DAM
BORING LOGS
MAY & JUNE 1963


1-5'-0" x 2'-6'-0" Sections of 46" R.C. Column 17'-0" High

1-5'-0" x 2'-6'-0" Sections of 46" R.C. Column 17'-0" High

1-5'-0" x 2'-6'-0" Sections of 46" R.C. Column 17'-0" High




PLAN - WETWELL
Scale: 1/4" = 1'-0"




PLAN

Note Slope Base Slab to drain toward pump




SECTION A-A
Scale: 1/4" = 1'-0"




SECTION A-A
DETAILS OF LIFT STATION
Scale: 1/4" = 1'-0"

NOTES

1. Structural design and the ACP Code
2. Backfill against walls 3,000 p.s.i. 28-day
3. For location of p. see Dwg NS 4368-1
4. Design of walls without surcharge
5. Reinforcing bars grade for new be conforming to ACP
6. All exposed edges
7. Structural steel American Institute of Steel Construction and
8. Structural steel
9. All structural steel
10. 2" Fasteners for
11. Entire Ladder after 100' test
12. All holes for
13. Fasteners for Ladder



LAKE INFLOW-OUTFLOW HYDROGRAPHS



PROPOSED DAM SITE

SUBSURFACE INVESTIGATION
&
LABORATORY ANALYSIS

FOR

LAKE SAINT LOUIS ESTATES, INC.
R.P. 2, - O'FALLON, MISSOURI

BY

BROWNING TESTING LABORATORIES, INC.
ROUTE 2, HWY. 54 NORTH
FULTON, MISSOURI 65251
(314) 642-5719

CHART 2-1

Casing used

Water Level 3.51 at 0 hrs.

Casing used.

Surface Elev.

SS Size _____ Wt of Hammer _____

Sheet 1 of 9

[illegible]

CHART 2-2

Revised, Hwy. 54 North
FULTON, MISSOURI 65251
(314) 411-2-5719

Water Level 9.0' at 2 hrs.

Rif No. 004E-58

Surface Elev. _____ SS Size _____ Wt of Hammer _____

Job No. 228

85-02-5-2100

Steel 2 of 9

Wilf of Hammer

Size SS

1

Rev. _____

Surface

FOR LA:3 St. Louis

[illegible]

CHART 2-3

Route 2, Hwy. 54 North
FULTON, MISSOURI 65231
(314) MI 2-5719

Job No. 228

Date 5-21-68

Sheet 3 of 9

Water Level at Hrs.

Casing used 25.0'

Rig No. CME-55

Surface Elev. SS Size Wt of Hammer

BORING NO. 3 (4500') FOR LAKE ST. LOUIS										WEATHER	TEMP.	ABBREVIATIONS
Sample No.	Depth		From Elevation	To Elevation	Distance	Method	Penetration Record				Site:	Color - Moisture - Material - Consistency
	From	To					Hydraulic Pressure	Time Interval	Number of Blows	Length Recovered		
	0.0	4.0	477.3		4.0	A					Proposed Dam Site	P.T.-Flash Test W.O.-Wash Out S.T.-Shelby Tube S.S.-Spill Spoon D.B.-Diamond Bit C.-Core R.B.-Rock Bit A.-Auger
	4.0	6.0			2.0	ST				2.0	" " " " " "	Lt. brown, lt. gray, moist silty clay, soft
	6.0	9.0			3.0	A					" " " " " "	" " " " " "
	9.0	10.0			1.0	ST				0.6	Sandy silty clay, wet, soft.	
	10.0	14.0			4.0	A					Gray silty clay with sand stringers, and decayed plant life, wet, soft.	
	14.0	16.0			2.0	ST				2.0	" " " " " "	" " " " " "
	16.0	19.0			3.0	A					" " " " " "	" " " " " "
	19.0	20.0			1.0	ST				0.6	" " " " " "	" " " " " "
	20.0	23.5			3.5	A					Gray sandy clay and limestone cobbles, wet, hard.	
	23.5	25.0		452.0	1.5	RB					Cherty limestone	

CHART 2-4

Route 2, Hwy. 54 North
FULTON, MISSOURI 65251
(314) AL 2-5719

Date _____

6 10 4 12345

Water Level _____ at _____ Mrs. _____

Casing used.

SS Size _____ Wt of Hammer _____

Rig 310

2025/12/13

[illegible]

CHART 2-1

Rig No. CME-55 Job No. 228
 Surface Elev. _____ Date 5-21-68
 Water Level _____ at _____ Hrs.
 Casing used 25'
 SS Size _____ Wt of Hammer _____ Sheet 5 of 9

BORING NO. 4 (3400) FOR Lake St. Louis										WEATHER clear		TEMP. 70°		ABBREVIATIONS	
Sample No.	Depth		From Elevation	To Elevation	Distance	Method	Penetration Record			Site:	Proposed Dam Site R.R. 2, O'Fallon, Missouri SAMPLE DESCRIPTION Color - Moisture - Material - Consistency	F.T.-Fish Tail W.O.-Wash Out S.T.-Shelby Tube S.S.-Split Spoon D.B.-Diamond Bit C. -Core R.B.-Rock Bit A. -Auger			
	From	To					Hydraulic Pressure Psi	Time Interval Sec	Number of Blows				Length Recovered Feet		
	0.0	4.0	479.38		4.0	A							Lt. brown-lt. gray mottled, silty clay, moist soft.		
	4.0	6.0			2.0	ST				" " " " " "			"		
	6.0	9.0			3.0	A				" " " " " "	"				
	9.0	11.0			1.0	ST				" " " " " "	"				
	11.0	13.0			1.0	A				" " " " " "	"				
	13.0	14.0			1.0	A				Gray, sandy silt, decayed plant, vet, soft.					
	14.0	15.0			2.0	ST				" " " " " "	"				
	16.0	25.0		454.38	9.0	A				Gray, sandy silt, cobbles, vet, soft.					
	25.0	30.0			5.0	RB				Lt. brown, weathered limestone with chert.					
										Bottom on cherty limestone.					
										Pressure test 10.0' - 45 gal. 2 min.					
										Pressure test 28.0' - 30 gal. 2 min.					

MISSOURI SUPPLY
FULTON, MISSOURI 65251
(314) 2-5719

MISSOURI SUPPLY

Job No. 228

Water Level 11.5 at 12 hrs.

Rig No. CKE-55

Casing used

Date 5-28-68

Surface Elev.

SS Size Wt of Hammer

Sheet 6 of 9

BORING NO. 5 (2-25) FOR Lake St. Louis				Penetration Record			Distance Feet	To Elevation	From Elevation	Depth		Weather	TEMP.	ABBREVIATIONS
Sample No.	From	To		Hydraulic Pressure Psi	Time Interval Sec	Number of Blows	Length Recovered Feet							
	0.0	4.0	479.61					4.0	A					
	4.0	6.0					2.0	2.0	ST					
	6.0	9.0						3.0	A					
	9.0	11.0					2.0	2.0	ST					
	11.0	14.0						3.0	A					
	14.0	16.0					1.0	2.0	ST					
	16.0	26.0						10.0	A					
	26.0	28.0						2.0	RB					
	28.0	34.0						6.0	RB					
CHART 2-														

Site:
Proposed Dam Site
R.R. 2,
O'Fallon, Missouri
SAMPLE DESCRIPTION
Color - Moisture - Material - Consistency

Lt. Brown, lt. gray mottled, silty loam,
wet, soft.
"
"
"
"
Lt. brown, sand and silt, wet, soft.
"
"
Lt. brown, sand and gravel, weathered
limestone, wet.
"
"
Lt. brown, weathered limestone with seams
to 28.0 ft. and limestone and chert to 34.0
"
Pressure test 12.0' - 45 gal. 3 min.

ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED

Water Level $\frac{44}{}$ at $\frac{0}{}$ Hrs.

Casing used - 191

Sheet 7 of 9

File No. C-15-55

Source: <https://www.irs.gov/efile/efile-1041-essentials>

[illegible]

CHART 2-8

FULTON, MISSOURI 65251
(314) MI 2-5719

Job No. 228

Date: 6-5-68

Steel 8: 0/9

[illegible]

CHART 2-9

Route 2, Hwy. 54 North
FULTON, MISSOURI 65251
(314) 412-5719

Water Level _____ at _____ Mrs. _____

Rip No. C/E-55

Casing used 61

Surface Elev.

SS size _____ Wt of Hammer _____

Job No. 228

Date 6-11-68

Sheet 9 of 9

[illegible]

CHART 2-10

Water Level _____ at _____ Hrs.

Casing used.

Fig No. CHE-55

Surface Elec: _____ SS Size _____ Wt of Hammer _____

W. of Hammer

-27:5 SS

BORING NO. 1.2 and 3 FOR Lake St. Louis

[illegible]

CHART 2-11

Route 2, Hwy. 55 North
FULTON, MISSOURI 65251
(314) 312-5719

Job No. 228
Date 6-12-68
Sheet 2 of 2

Water Level at 11rs.
Casing used
SS Size Wt of Hammer

Rig No. CHE-55

Surface Elev.

BORING NO. 1, 2, and 3 FOR LOCK & ST. LOUIS				WEATHER Clear			TEMP. 80°			ABBREVIATIONS		
Sample No.	Depth		From Elevation	To Elevation	Distance Feet	Method	Penetration Record			Site: Borrow Area East Proposed Dam Site R.R. 2, - O'Fallon, Missouri	SAMPLE DESCRIPTION Color - Moisture - Material - Consistency	F.T.-Fish Tail W.O.-Wash Out S.T.-Shelby Tube S.S.-Split Spoon D.B.-Diamond Bit C.-Core R.B.-Rock Bit A.-Auger
	From	To					Hydraulic Pressure Psi	Time Interval Sec	Number of Blows	Length Recovered Feet		
1	0.0	2.5			A						Lt. brown, silty clay, soft, moist.	
	2.5	5.0			A						Reddish brown, silty clay, stiff, moist.	
2	0.0	3.0			A						Lt. brown, silty clay, soft, moist.	
	3.0	9.0			A						Reddish brown, silty clay, boulders, stiff, moist.	
	9.0				A						Bottom on Limestone.	
3	0.0	3.0			A						Lt. brown, silty clay, soft, moist.	
	3.0	7.5			A						Reddish-brown, silty clay, boulders, stiff, moist.	
	7.5				A						Bottom on Limestone.	

BROWNING TESTING LABORATORIES, INC.
Route 2, Hwy. 54 North
Potosi, Missouri 65251
(314) 642-5719

DATA SUMMARY SHEET

JOB NO. 228

LABORATORY TESTS

DATE 6-18-68

Borrow Area West
Lake St. Louis

ATTERBERG LIMITS:

HOLE NO.

DEPTH FT.

6 - 28

0 - 6

LIQUID LIMIT

50%

28%

PLASTIC LIMIT

22%

20%

PLASTIC INDEX

28

8

SHRINKAGE LIMIT

8

18

NATURAL MOISTURE

37%

18%

AASHTO
SOIL CLASSIFICATION

A-7-6

A-6

FAA
SOIL CLASSIFICATION

E-8

E-7

UNIFIED
SOIL CLASSIFICATION

CH

CL

REMARKS:

CHART 2-13



Soil Sampling
Core Drilling
Site Explorations
Pressure Grouting
Geological Investigations

5121 NO. LINDBERGH BLVD. • BRIDGETON, MO. 63042 • 314-731-1111

23 July 1969

Horner & Shifrin, Inc.
Consulting Engineers
1221 Locust Street
St. Louis, Missouri 63103

Attention: Mr. Don Lochmoeller

RE: Test Drilling Report
and Pressure Test Data
For Lake St. Louis
Project, St. Charles
County, Missouri

Dear Don:

Per your instructions we have completed the test drilling along the center line of the proposed dam and spillway section. Results of this investigation are enclosed for your review. Testing procedure was performed under your instruction letter of July 3, 1969. It was quite apparent throughout the duration of the water pressure tests that the bedrock appears quite sound and continuous. In addition to your instructions we initiated the use of a water meter to verify that the formation was not taking water, during the constant pressure test. It should be noted that before the test section time that all pressures were held for a period of ten minutes before the initial readings were taken. In all cases the pressure readings held constant or increased slightly, within the accuracy of the pressure test gauge.

For your information our diamond setting for NXM series coring is 2 7/8" O.D.. The cores taken on this project will be held in our warehouse until notice is given to deliver to your preference.

Per your request we are at this time working-up a bid on a per cubic yard basis, with an estimated 35,000 cubic yards of limestone excavation. We are bidding on the basis of drilling and shooting with the removal of the material shot, by others.

Thank you for calling on Test Drilling Service Company for work. If you have any questions concerning the enclosed data, please contact us at your convenience. With best

Very truly yours,

TEST DRILLING SERVICE COMPANY



Donald L. Ramsey, Geologist

CHART 2-14

DRILLING SERVICE COMPANY

PHONE: 314-731-1111

5121 NO. LINDBERGH BLVD.

BRIDGETON, MO. 63042

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS

Job No. 247

Boring 2 Location PER CLIENT INSTRUCTION Surface El. 510 : 514.6

Drilling Co. TEST DRILLING SERVICE CO. Boring Type NXM CORE

Date 7-14-69

Rig 63

Inspector TED LEAR

CORE RUN		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST		
From	To					Pac. Loc. (ft.)	Pressure (Psi)	Inflow (Gpm)
					0.0 - 7.0'			
					Red Residual Stiff Clay W/Heavy Gravel & Boulders			
507.6	7.0	10.0	3.0	1.9	63.5			
					7.0 - 9.0'			
504.6	10.0	15.0	5.0	4.0	80.0			
					Medium Gray, Hard dense, Medium Bedded Fine to Medium Crystalline Limestone w/chert Nodules			
499.6	15.0	20.0	5.0	5.0	100			
					9.0' - 11.0'			
494.6	20.0	25.0	5.0	5.0	100			
					Red Gravelly Clay			
489.6	25.0	30.0	5.0	5.0	100			
					11.0 - 18.8'			
479.6	35.0	40.0	5.0	5.0	100			
					Medium Gray Hard Dense Medium Bedded, Medium Crystalline Limestone with Numerous Chert Band & Nodules up to 8" in Dimension			
474.6	40.0	45.0	5.0	5.0	100			
					18.8 - 24.0'			
469.6	45.0	50.0	5.0	5.0	100			
					Lt. Gray, Medium to Massive Bedded, Coarsely Crystalline, Hard Fossiliferous Limestone w/Styolitic Partings			
					24.0 - 35.5'			
					Light Gray, Thin to Medium Bedded, Coarsely Crystalline, Hard Fossiliferous Limestone w/Numerous Chert Bands & Nodules up to 10" Dimension			
					35.5 - 39.0'			
					Lt. Gray, Medium to Massive Bedded, Coarsely Crystalline, Hard Fossiliferous Limestone w/Styolitic Partings			
					39.0 - 50.0'			
					Light Gray, Thin to Medium Bedded, Coarsely Crystalline, Hard Fossiliferous Limestone w/Numerous Chert Bands & Nodules up to 6" Dimension & Numerous Buff Weathered Portions			
					50.0' Bottom of Test Hole Per Client Instruction			

Drilling Fluid CLEAR WATER Casing 12.0' Press. Gage Loc. @ Gr. Surf.
Ground Water Depth 27.0' Date 7-17-69 Method Det. STEEL TAPE
Remarks SEE ATTACHED PRESSURE TEST SHEETS NO. 2 THRU 6

CHART 2 'S

DATE 3 OF 6
PAGE 7-17-69

DAM SITE LAKE ST. LOUIS DIVISION PERUQUE CK 2 43
LOCATION OF HOLE PER CLIENT INSTRUCTION
CONTRACTOR TEST DRILLING SERVICE CO. DRILLING C. STEVENS 510

[illegible]

* UNABLE TO OBTAIN ANY GAGE PRESSURE AT START OF TEST

[illegible]

D. L. RAMSEY

CHART 2-17

7-17-69

DAM SITE LAKE ST. LOUIS RIVER PERQUEE CK. DIST. NO. 2 DIST. NO. 43
LOCATION OF HOLE PER CLIENT INSTRUCTION
CONTRACTOR TEST DRILLING SERVICE CO. DRILLER J. STEVENS TOP OF HOLE 510±

[illegible]

* UNABLE TO OBTAIN ANY GAGE PRESSURE AT START OF TEST

[illegible]

D. L. RAMSEY

CHART 2-18

DATE 5 or 6
7-17-69

DAM SITE LAKE ST. LOUIS RIVER PERDUQUE CK. DIST. NO. 2. REG. NO. 43
LOCATION OF HOLE PER CLIENT INSTRUCTION
CONTRACTOR TEST DRILLING SERVICE CO. DRILLER C. STEVENSON REV. 100 OF 100 510±

[illegible]

* UNABLE TO OBTAIN ANY GAGE PRESSURE AT START OF TEST

[illegible]

CHART 2-19

7-17-69

DAM SITE LAKE ST. LOUIS RIVER PERDUE CK. HOLE NO. 2 HOLE NO. 43
LOCATION OF HOLE PER CLIENT INSTRUCTION
CONTRACTOR TEST DRILLING SERVICE CO. DRILLER C. STEVENS TEST OF HOLE 510±

[illegible]

W UNABLE TO OBTAIN ANY GAGE PRESSURE AT START OF TEST

[illegible]

D. L. RAMSEY

CHART 2-20

DRILLING SERVICE COMPANY

PHONE: 314-731-1111

5121 NO. LINDBERGH BLVD.

BRIDGETON, MO. 63042

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS

Job No. 247

Boring 3 Location PER CLIENT INSTRUCTIONS

Surface El. 476.7

Drilling Co. TEST DRILLING SERVICE CO.

Boring Type NXM CORE

Date 7-8-69

Rig 63

Inspector DON RAMSEY

CORE RUN		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST			
From	To					Pac. Loc. (Ft.)	Bot. Hole (Ft.)	Pressure (Psi)	Int. (Cp)
					0.0-13.0'				
					Fill Control Section				
					13.0-27.0'				
27.0	29.5	2.5	2.3	92	Alluvial Deposit - Stratified Sands, Gravels w/ Silt & Clayey Silt Matrix				
					27.0-34.6'				
29.5	37.0	7.5	7.5	100	Medium Gray, Medium To Massive Bedded Hard, Dense Medium to Coarsely Crystalline Fossiliferous Limestone w/ Scattered Few Chert Nodules Up to 2" Dimension				
					34.6-35.3'				
					Solid Chert Band				
					35.3-37.0'				
					Medium Gray, Fresh, Medium Crystalline, Hard, Dense Medium Bedded, Styolitic Limestone - Fossiliferous				
					37.0' Bottom of Boring Per Client Instruction				

Drilling Fluid CLEAR WATER

Casing 27.0' Press. Gage Loc. @ Gr. Surf.

Ground Water Depth 13.0'

Date 7-8-69

Method Det. STEEL TAPE

Remarks SEE WATER PRESSURE TEST SHEETS 2 THRU 3

CHART 2-21

SHEET 1 of 3

Sheet 2 of 3
Date 7-17-69

DAM SITE LAKE ST. LOUIS RIVER PERUQUE CK HOLE NO. 3 HOLE NO. 43
LOCATION OF HOLE PER CLIENT INSTRUCTION
CONTRACTOR TEST DRILLING SERVICE CO. DRILLER C. STEVENS REVIEW TOP OF HOLE

[illegible]

* UNABLE TO OBTAIN ANY GAGE PRESSURE AT START OF TEST

[illegible]

OBSERVED BY **D. L. RAMSEY**

CHART 2-22

3 on 3
7-17-69

DAM SITE LAKE ST. LOUIS RIVER PERUQUE CK

LOCATION OF HOLE PER CLIENT INSTRUCTION

CONTRACTOR TEST DRILLING SERVICE CO. PHILLIP C. STEVENS

[illegible]

ELEV TOP ROCK -
BOTTOM HOLE -

* UNABLE TO OBTAIN ANY GAGE PRESSURE AT START OF TEST

[illegible]

Dist. by the

D. L. RAMSEY

CHART 2-23

7-20-69

4 43

CONTRACTOR TEST DRILLING SERVICE CO. DRILLER C. STEVENSON

[illegible]

ELEV TOP ROCK -
BOTTOM HOLE -

X UNABLE TO OBTAIN ANY GAGE PRESSURE AT START OF TEST

[illegible]

DISCOVERED BY D. L. RAMSEY

CHART 2-25

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS Job No. 247
Boring 4 Location PER CLIENT INSTRUCTION Surface El. 487.7
Drilling Co. TEST DRILLING SERVICE CO. Boring Type NXM CORE
Date 7-9-69 Rig 63 Inspector DON RAMSEY

CORE RUN		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST		
From	To					Pac. Loc. (Ft.)	Pressure (Psi)	Inflow (Gpm)
					0.0-37.0'			
					Control Fill Section			
					Free Water Entry @ Contact			
					W/Bedrock			
37.0	42.5	5.5	5.5	100	37.0-42.5'			
					Fresh Medium Gray Thin to Medium			
					Bedded Coarsely Crystalline,			
					Hard Dense Fossiliferous			
					Styolitic Limestone W/Scattered			
					Few Nodules of Chert			
					42.5' Stopped Hole Due to Very			
					Hard Chert Inclusion Which Could			
					Not be Cored			

Drilling Fluid CLEAR WATER Casing 37' Press. Gage Loc. Gr. Surface
Ground Water Depth 23.0' Date 7-9-69 Method Det. STEEL TAPE
Remarks SEE WATER PRESSURE TESTING SHEET 2 of 2

CHART 2-24

SHEET 1 of 2



5121 NO. LINDBERGH BLVD. • BRIDGETON, MO. 63042 • 314-731-1111

Soil Sampling
Core Drilling
Site Explorations
Pressure Grouting
Geological Investigations

July 1, 1970

Horner & Shifrin, Inc.
5200 Oakland
St. Louis, Missouri 63110

Attention: Mr. Donald C. Lochmoeller

RE: Core Drilling Report
For Spillway Design
Lake St. Louis
St. Charles County

Gentlemen:

We are submitting three (3) copies of our core boring report pertaining to the subject project site.

A total of eleven (11) detailed core borings were drilled at your direction and are shown on the site plan, Figure 1. Our boring logs, Figure 2 thru 12 present the detailed description of the material encountered and the core recovery records. Special notes on loss of drill water circulation are reported for each boring drilled.

We hope the information enclosed is as complete as you desire. If you have any questions concerning this information, please contact us at your convenience and we will be more than happy to meet with you. Thank you for calling on Test Drilling Service Company for this work.

With Best Regards,

TEST DRILLING SERVICE COMPANY


Donald L. Ramsey
Vice-President

DLR/bh

Enc.-

TEST DRILLING REPORT DRILLING SERVICE CO.

5121 NO. LINDBERGH BLVD. • 314-731-1111 • BRIDGETON, MO. 63042

Client Horner & Shifrin

Date of Report 7-1-70


Address 5200 Oakland, St. Louis, Missouri 63110

We Have Completed Exploratory Test Drilling Work For You at

Lake St. Louis Spillway

As Outlined Below. Detailed Results of All Boring Is Attached Hereto.

Test Hole Location Plan
Scale 1" = 100'



Job No. _____

Sheet _____ of _____

CHART 2-27


10-A104 614

HORNER AND SHIFRIN INC ST LOUIS MO F/8 13/13
NATIONAL DAM SAFETY PROGRAM. LAKE ST. LOUIS DAM (MO 10545) MISS-ETC(U)
MAY 78 DACW43-79-C-0047

NL

UNCLASSIFIED

2
AL
ADDRESS



ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS - SPILLWAY CORING Job No. 70-62
Boring 1 Location 11+00, 35' LEFT Surface El. 499.73'
Drilling Co. TEST DRILLING SERVICE CO. Boring Type AY CORE
Date 6-5-70 Rig CME NO. 59 Inspector E.L.B.

CORE RUN (50-53)		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST		
From	To					Pac. Loc. (Ft.)	Pot. Hole(Ft.)	Pressure (Psi)
3-4	5-5	28"	20"	71	0100"-3112" Broken rock			
5-5	13-4	92"	87"	93	3112"-10110" Gray limestone w/ trace chert & oolite. 1" decomposed zone			
13-4	23-4	120"	102"	91	10110"-23116" Gray limestone w/ chert inclusions up to 3" thick			
23-4	33-4	120"	112"	92	23116"-31112" Gray to gray buff, slightly saturated, silt, limestone w/ oolite, chert inclusions up to 2" thick			
33-4	29-2	77"	66"	78	31112"-22119" Gray limestone w/ chert inclusions up to 3" thick & oolite. thin, decomposed zone			
					32119" Bottom of boring			

Drilling Fluid CLEAR WATER Casing 3 1/4" Press. Gage Loc. _____
Ground Water Depth _____ Date _____ Method Det. _____
Remarks No drill water circulation loss throughout coring operations.

CHART 2-28

FIG. 2

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS - SPILLWAY CORING Job No. 72-62
Boring 5 Location 11+00, 72' LEFT Surface El. 498.5'
Drilling Co. TEST DRILLING SERVICE CO. Boring Type AM CONC
Date 6-1-70 Rig CHEV. NO. 59 Inspector D.L.R.

CORE RUN (Feet)		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST		
From	To					Pac. Loc. (Ft.) Est. Hole(Ft.)	Pressure (Psi)	Inflow (Gpm)
0-1	2-3	20"	15"	67	0'0"-0'4" Broken shot rock			
2-3	12-1	113"	54"	47	0'4"-1'2" Gray Limestone w/ thin chert inclusions			
12-1	22-1	120"	116"	97	1'2"-2'0" Decomposed limestone			
22-1	32-1	120"	16"	13	2'0"-6'7" Gray Limestone w/ trace chert			
32-1	39-9	80"	13"	16	6'7"-11'6" Decomposed limestone			
					11'6"-23'5" Gray limestone w/ chert inclusions up to 5" thick			
					23'5"-38'9" Buff, highly weathered, silty decomposed limestone			
					38'9" Bottom of boring per client instructions			

Drilling Fluid CLEAR WATER Casing NONE Press. Gage Loc. _____
Ground Water Depth _____ Date _____ Method Det. _____
Remarks No drill water circulation loss throughout drilling operations.

CHART 2-29

ETG 3

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS - SPIRLWAY CORING Job No. 70-69
Boring 7 Location 10+00, 35' LEFT Surface El. 169.0'
Drilling Co. TEST DRILLING SERVICE CO. Boring Type AX CORZ
Date 5-27-70 Rig CME NO. 59 Inspector D.L.R.

[illegible]

Drilling Fluid CLEAR WATER Casing None Press. Gage Loc. _____
Ground Water Depth _____ Date _____ Method Det. _____
Remarks _____

CHART 2-30
FIG. 4

DRILLING SERVICE COMPANY

PHONE: 314-731-1111

5121 NO. LINDBERGH BLVD.

BRIDGETON, MO. 63042

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS - SPILLWAY CORING Job No. 70-69
 Boring 7-A Location 10+00, 75' LEFT Surface El 198.7'
 Drilling Co. TESS DRILLING SERVICE CO. Boring Type IX & AX CORE
 Date 5-12-70 & 6-2-70 Rig CME NO. 59 Inspector D.L.R.

CORE RUN (Feet-In)		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST		
From	To					Loc. (Ft.)	Pressure (Psi)	Inflow (Gpm)
0-6	5-0	54"	100"	82	010"-016" Overburden - Broken rock & clay			
5-0	9-6	54"	54"	100	016"-111" Gray limestone w/ trace chert			
9-6	15-7	73"	73"	100	111"-1110" Decomposed limestone			
15-7	25-7	120"	70"	58	1110"-2110" Gray limestone w/ occas. thin chert inclusions			
25-7	32-10	37"	30"	57	2110"-2117" Gray limestone w/ chert inclusions up to 1/4" thick w/ soft decomposed strata below			
32-10	39-0	74"	54"	73	2117"-2117" Gray limestone w/ chert inclusions up to 1/4" thick w/ decomposed strata below			
					2117"-3910" Buff to buff gray, slightly weathered silty limestone w/ chert inclusions up to 1/4" thick w/ decomposed strata below			
					3910"-3912" Bottom of boring			

Drilling Fluid CLEAR WATER Casing NONE Press. Gage Loc. _____
 Ground Water Depth _____ Date _____ Method Det. _____
 Remarks Used "X" Core to 15'7" on 5-12-70, then changed to AX Core to 39'0" on 6-2-70.

No drill water circulation loss throughout coring operations. CHART 23

DRILLING SERVICE COMPANY

PHONE: 314-731-1111

5121 NO. LINDBERGH BLVD.

BRIDGETON, MO. 63042

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS - SPILLWAY CORING Job No. 70-60
 Boring 7-B Location 10+00, 115' LEFT Surface El. 425.7'
 Drilling Co. TECH DRILLING SERVICE CO. Boring Type 4" CORE
 Date 5-28-70 Rig CME NO. 52 Inspector D.L.B.

CORE RUN (ft-in)		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST		
From	To					Fac. Loc. (ft)	Pressure (Psi)	Inflow (Gpm)
1-0	11-7	121"	74"	53	0-10" Overburden - Shot rock			
11-7	21-9	120"	100"	82	11-6" - 11-9" Gray limestone w/ trace chert			
21-9	25-1	92"	1-2"	13	7-8" decomposed seams below			
25-1	35-9	70"	60"	85	21-9" - 27-13" Gray limestone w/ chert			
					inclusions up to 6" thick & soft			
					decomposed seams below			
					11-6" - 11-9"			
					21-9" - 27-13"			
					27-13" - 35-9" Gray limestone w/ chert			
					inclusions up to 3" thick & occas. thin			
					decomposed seams up to 3/4" thick			
					35-9" Bottom of boring			

Drilling Fluid CLEAR WATER Casing 1 1/2" Press. Gage Loc. _____
 Ground Water Depth _____ Date _____ Method Det. _____
 Remarks No drill water circulation loss throughout the coring
operations.

CHART 2-32

FIG. 6

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS - SPILLWAY CORING Job No. 70-67
Boring 10 Location R+75, 25' LEFT Surface El. 1097.8'
Drilling Co. TEST DRILLING SERVICE CO. Boring Type AY CORE
Date 5-26-70 Rig CITE NO. 52 Inspector D.L.B.

CORE RUN (11-12)		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST		
From	To					Loc. Loc. (ft.)	Pressure (Psi)	Inflow (Gpm)
1-0	1-1	11"	11"	100	010"-110" Overburden - loose shot rock			
1-1	2-1	60"	58"	97	110"-111" Gray limestone w/ trace chert			
2-1	12-3	100"	100"	100	111"-251" Gray limestone w/ numerous chert inclusions up to 8" thick			
10-3	25-5	26"	26"	100	251"-321" buff gray to buff, slightly weathered, silty limestone w/ chert inclusions up to 2" thick			
25-5	31-2	58"	53"	100	321"-381" Gray limestone w/ chert inclusions 1, 2 to 3" thick			
31-2	38-0	58"	56"	97	381" Bottom of boring			
					NOTE: No water circulation loss throughout coring operations			

Drilling Fluid CLEAR WATER Casing NONE Press. Gage Loc. _____
Ground Water Depth _____ Date _____ Method Dot. _____
Remarks _____

CHART 2-33

FIG. 7

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS - SPIRITWAY CORING Job No. 70-69
Boring 11 Location 7+50, 115' LEFT Surface El. 518.5'
Drilling Co. TEST DRILLING SERVICE CO. Boring Type AY CORE
Date 6-22-70 Rig CME NO. 59 Inspector D.L.R.

CORE RUN (1-1-77)		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST		
From	To					Prc. Loc. (Ft.)	Bot. Hole (Ft.)	Pressure (Psi)
					0'0"-34'3" Overburden			
54-3	144-3	120"	50"	1/2	34'3"-144'3" Gray to buff gray limestone w/ numerous decomposed horizons			
					144'3"-Bottom of boring per client instruction			
					</			

Drilling Fluid CLEAR WATER Casing 3 1/2" Press. Gage Loc. _____
Ground Water Depth _____ Date _____ Method Det. _____
Remarks _____

CHART 2-34

ITC

DRILLING SERVICE COMPANY

PHONE: 314-731-1111

5121 NO. LINDBERGH BLVD. BRIDGETON, MO. 63042

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS - SPILLWAY CORING Job No. 70-69
 Boring 15 Location 6+50, 35' LEFT Surface El. 425.3'
 Drilling Co. TEST DRILLING SERVICE CO. Boring Type AX CORE
 Date 5-25-70 Rig CME NO. 59 Inspector D.L.R.

COPE RUN (Feet)		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST		
From	To					Sec. Loc. (Feet)	Pressure (Psi)	Inflow (Gpm)
2-2	1-2	26"	20"	77	0-10" - 2-10" Overburden			
1-2	0-1	6"	52"	87	2-10" - 2-110" Gray limestone - Trace chert 1/2" thin, buff partings			
0-1	0-0	70"	70"	100	2-110" - 3-12" Soft, decomposed limestone - lost water circulation			
0-0	0-0	60"	35"	58	3-12" - 4-18" Gray limestone - Trace chert 1/2" thin, buff partings			
0-0	0-0	60"	60"	100	(NOTE - Set NK casing to 4'12")			
0-0	0-0	56"	56"	100	4-18" - 5-11" Soft, decomposed limestone - no water loss			
0-0	0-0	16"	16"	100	5-11" - 5-18" Gray limestone - Trace chert 1/2" thin, buff partings			
					5-18" - 6-12" Soft, decomposed limestone - no water loss			
					6-12" - 25-17" Gray limestone w/ chert inclusions up to 8" thick			
					25-17" - 27-10" Buff, weathered, silty limestone - lost 30" water return			
					27-10" - 33-12" Gray limestone w/ chert inclusions up to 10" thick - Vertical fracture throughout section			
					33-12" - 35-0" Buff, gray limestone w/ chert inclusions to 6" thick			
					35-0" Bottom of boring			

Drilling Fluid Clear water Casing 4-12" Press. Gage Loc. _____
 Ground Water Depth _____ Date _____ Method Det. _____
 Remarks: 4 Bearings on core barrel were damaged on this run - Formation
cored solid w/ poor recovery due to grinding core
No drill water circulation loss throughout coring operations.

CHART 2-35
FIG. 9

DRILLING SERVICE COMPANY

PHONE: 314-731-1111

5121 NO. LINDBERGH BLVD. BRIDGETON, MO. 63042

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS - SPILLWAY CORING Job No. 70-69
 Boring 16 Location 6+50 ON CENTERLINE Surface El. 495.71
 Drilling Co. TEST DRILLING SERVICE CO. Boring Type AY CORZ
 Date 5-25-70 Rig CUE NO. 59 Inspector D.J.B.

CORE RUN (Feet)		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST		
From	To					Pressure (Psi)	Inflow (Gpm)	
0-0	1-5	17"	56"	94	110"-117" Gray limestone w/ trace chert (light matrix)			
1-5	2-9	14"	60"	100	117"-2117" Gray limestone w/ chert inclusions up to 3" thick - light matrix			
2-9	31-7	22"	22"	100	2117"-3110" Buff gray to buff slightly weathered limestone w/ numerous small inclusions to 1/4" thick & occa. thin vertical fractures (10' water circulation loss)			
31-7	31-9	2"	58"	98				
31-9	40-9	10"	60"	100				
40-9	41-9	10"	60"	100				
41-9	43-9	18"	68"	100	3519" Bottom of boring			

Drilling Fluid CLEAR WATER Casing NONE Press. Gage Loc. _____
 Ground Water Depth _____ Date _____ Method Det. _____
 Remarks No drill water circulation loss throughout coring operations.

CHART 2-36

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS - SPILLWAY CORING Job No. 70-62
Boring 17 Location 7+50 ON CENTERLINE Surface El 197.6'
Drilling Co. TEST DRILLING SERVICE CO. Boring Type AY CORE
Date 5-12-70 Rig CME NO. 59 Inspector D.I.R.

CORE RUN					CLASSIFICATION	PRESSURE TEST		
From	To	Total Run	Core Recovery	Percent Recovery		Sec. Loc. (Ft.)	Pressure (Psi)	Inflow (Gpm)
1-10	2-10	52"	100"	80	0100-0511" Gray Limestone w/ numerous short inclusions up to 1" thick & soft			
2-10	3-10	60"	60"	100	Decomposed section, later.			
3-10	4-10	60"	60"	70	2100-2110" = 10"			
4-10	5-10	60"	60"	100	3110-3110" = 0"			
5-10	6-10	60"	60"	100	4110-4110" = 0"			
6-10	7-10	60"	60"	100	5110-5110" = 0"			
7-10	8-10	60"	60"	100	6110-6110" = 0"			
8-10	9-10	60"	60"	100	7110-7110" = 0"			
9-10	10-10	60"	60"	100	8110-8110" = 0"			
10-10	11-10	60"	60"	100	9110-9110" = 0"			
11-10	12-10	60"	60"	100	10110-10110" = 0"			
12-10	13-10	60"	60"	100	11110-11110" = 0"			
13-10	14-10	60"	60"	100	12110-12110" = 0"			
14-10	15-10	60"	60"	100	13110-13110" = 0"			
15-10	16-10	60"	60"	100	14110-14110" = 0"			
16-10	17-10	60"	60"	100	15110-15110" = 0"			
17-10	18-10	60"	60"	100	16110-16110" = 0"			
18-10	19-10	60"	60"	100	17110-17110" = 0"			
19-10	20-10	60"	60"	100	18110-18110" = 0"			
20-10	21-10	60"	60"	100	19110-19110" = 0"			
21-10	22-10	60"	60"	100	20110-20110" = 0"			
22-10	23-10	60"	60"	100	21110-21110" = 0"			
23-10	24-10	60"	60"	100	22110-22110" = 0"			
24-10	25-10	60"	60"	100	23110-23110" = 0"			
25-10	26-10	60"	60"	100	24110-24110" = 0"			
26-10	27-10	60"	60"	100	25110-25110" = 0"			
27-10	28-10	60"	60"	100	26110-2713" Buff gray to buff, slightly weathered, silty limestone w/ numerous short inclusions up to 5" thick			
28-10	29-10	60"	60"	100	2713" Bottom of boring			
29-10	30-10	60"	60"	100				
30-10	31-10	60"	60"	100				
31-10	32-10	60"	60"	100				
32-10	33-10	60"	60"	100				
33-10	34-10	60"	60"	100				
34-10	35-10	60"	60"	100				
35-10	36-10	60"	60"	100				
36-10	37-10	60"	60"	100				
37-10	38-10	60"	60"	100				
38-10	39-10	60"	60"	100				
39-10	40-10	60"	60"	100				
40-10	41-10	60"	60"	100				
41-10	42-10	60"	60"	100				
42-10	43-10	60"	60"	100				
43-10	44-10	60"	60"	100				
44-10	45-10	60"	60"	100				
45-10	46-10	60"	60"	100				
46-10	47-10	60"	60"	100				
47-10	48-10	60"	60"	100				
48-10	49-10	60"	60"	100				
49-10	50-10	60"	60"	100				
50-10	51-10	60"	60"	100				
51-10	52-10	60"	60"	100				
52-10	53-10	60"	60"	100				
53-10	54-10	60"	60"	100				
54-10	55-10	60"	60"	100				
55-10	56-10	60"	60"	100				
56-10	57-10	60"	60"	100				
57-10	58-10	60"	60"	100				
58-10	59-10	60"	60"	100				
59-10	60-10	60"	60"	100				
60-10	61-10	60"	60"	100				
61-10	62-10	60"	60"	100				
62-10	63-10	60"	60"	100				
63-10	64-10	60"	60"	100				
64-10	65-10	60"	60"	100				
65-10	66-10	60"	60"	100				
66-10	67-10	60"	60"	100				
67-10	68-10	60"	60"	100				
68-10	69-10	60"	60"	100				
69-10	70-10	60"	60"	100				
70-10	71-10	60"	60"	100				
71-10	72-10	60"	60"	100				
72-10	73-10	60"	60"	100				
73-10	74-10	60"	60"	100				
74-10	75-10	60"	60"	100				
75-10	76-10	60"	60"	100				
76-10	77-10	60"	60"	100				
77-10	78-10	60"	60"	100				
78-10	79-10	60"	60"	100				
79-10	80-10	60"	60"	100				
80-10	81-10	60"	60"	100				
81-10	82-10	60"	60"	100				
82-10	83-10	60"	60"	100				
83-10	84-10	60"	60"	100				
84-10	85-10	60"	60"	100				
85-10	86-10	60"	60"	100				
86-10	87-10	60"	60"	100				
87-10	88-10	60"	60"	100				
88-10	89-10	60"	60"	100				
89-10	90-10	60"	60"	100				
90-10	91-10	60"	60"	100				
91-10	92-10	60"	60"	100				
92-10	93-10	60"	60"	100				
93-10	94-10	60"	60"	100				
94-10	95-10	60"	60"	100				
95-10	96-10	60"	60"	100				
96-10	97-10	60"	60"	100				
97-10	98-10	60"	60"	100				
98-10	99-10	60"	60"	100				
99-10	100-10	60"	60"	100				
100-10	101-10	60"	60"	100				
101-10	102-10	60"	60"	100				
102-10	103-10	60"	60"	100				
103-10	104-10	60"	60"	100				
104-10	105-10	60"	60"	100				
105-10	106-10	60"	60"	100				
106-10	107-10	60"	60"	100				
107-10	108-10	60"	60"	100				
108-10	109-10	60"	60"	100				
109-10	110-10	60"	60"	100				
110-10	111-10	60"	60"	100				
111-10	112-10	60"	60"	100				
112-10	113-10	60"	60"	100				
113-10	114-10	60"	60"	100				
114-10	115-10	60"	60"	100				
115-10	116-10	60"	60"	100				
116-10	117-10	60"	60"	100				
117-10	118-10	60"	60"	100				
118-10	119-10	60"	60"	100				
119-10	120-10	60"	60"	100				
120-10	121-10	60"	60"	100				
121-10	122-10	60"	60"	100				
122-10	123-10	60"	60"	100				
123-10	124-10	60"	60"	100				
124-10	125-10	60"	60"	100				
125-10	126-10	60"	60"	100				
126-10	127-10	60"	60"	100				
127-10	128-10	60"	60"	100				
128-10	129-10	60"	60"	100				
129-10	130-10	60"	60"	100				
130-10	131-10	60"	60"	100				
131-10	132-10	60"	60"	100				
132-10	133-10	60"	60"	100				
133-10	134-10	60"	60"	100				
134-10	135-10	60"	60"	100				
135-10	136-10	60"	60"	100				
136-10	137-10	60"	60"	100				
137-10	138-10	60"	60"	100				
138-10	139-10	60"	60"	100				
139-10	140-10	60"	60"	100				
140-10	141-10	60"	60"	100				
141-10	142-10	60"	60"	100				
142-10	143-10	60"	60"	100				
143-10	144-10	60"	60"	100				
144-10	145-10	60"	60"	100				
145-10	146-10	60"	60"	100				
146-10	147-10	60"	60"	100				
147-10	148-10	60"	60"	100				
148-10	149-10	60"	60"	100				
149-10	150-10	60"	60"	100				
150-10	151-10	60"	60"	100				
151-10	152-10	60"	60"	100				
152-10	153-10	60"	60"	100				
153-10	154-10	60"	60"	100				
154-10	155-10	60"	60"	100				
155-10	156-10	60"	60"	100				
156-10	157-10	60"	60"	100				
157-10	158-10	60"	60"	100				
158-10	159-10	60"	60"	100				
159-10	160-10	60"	60"	100				
160-10	161-10	60"	60"	100				
161-10	162-10	60"	60"	100				
162-10	163-10	60"	60"	100				
163-10	164-10	60"	60"	100				
164-10	165-10	60"	60"	100				
165-10	166-10	60"	60"	100				
166-10	167-10	60"	60"	100				
167-10	168-10	60"	60"	100				
168-10	169-10	60"	60"	100				
169-10	170-10	60"	60"	100				
170-10	171-10	60"	60"	100				
171-10	172-10	60"	60"	100				
172-10	173-10	60"	60"	100				
173-10	174-10	60"	60"	100				
174-10	175-10	60"	60"	100				
175-10	176-10	60"	60"	100				
176-10	177-10	60"	60"	100				
177-10	178-10	60"	60"	100				
178-10	179-10	60"	60"	100				
179-10	180-10	60"	60"	100				
180-10	181-10	60"	60"	100				
181-10	182-10	60"	60"	100				
182-10	183-10	60"	60"	100				
183-10	184-10	60"	60"	100				
184-10	185-10	60"	60"	100				
185-10	186-10	60"	60"	100				
186-10	187-10	60"	60"	100				
187-10	188-10	60"	60"	100				
188-10	189-10	60"	60"	100				
189-10								

Drilling Fluid CLEAR WATER Casing 11012 Press. Gage Loc. _____
Ground Water Depth _____ Date _____ Method Dot. _____
Remarks _____

CHART 2-37

ETA 11

DRILLING SERVICE COMPANY

PHONE: 314-731-1111

5121 NO. LINDBERGH BLVD. BRIDGETON, MO. 63042

ST. LOUIS COUNTY

FIELD BORING LOG

Project LAKE ST. LOUIS - SPIRITWAY CORING Job No. 70-69
 Boring 12 Location B-75 ON CENTERLINE Surface El. 103.1'
 Drilling Co. TB'S DRILLING SERVICE CO. Boring Type AY CORE
 Date 6-2-70 Rig CME NO. 59 Inspector D.L.R.

CORE RUN (50' - 51')		Total Run	Core Recovery	Percent Recovery	CLASSIFICATION	PRESSURE TEST		
From	To					Pac. Loc. (Ft.)	Pressure (Psi)	Inflow (Gpm)
1-7	11-0	22"	27"	93	11'7"-11'7" Broken shot rock			
11-0	11-0	34"	31"	91	11'7"-11'0" Gray limestone w/ occas. thin chert string			
11-0	19-9	105"	8"	8	11'0"-12'0" Buff, weathered, decomposed limestone w/ numerous chert inclusions			
19-9	29-9	120"	104"	87	12'0"-29'9" Gray to buff, gray limestone w/ chert inclusions up to 5" thick and decomposed seen betw. 28'0" to 29'8"			
29-9	38-2	101"	94"	93	29'9"-38'2" Bottom of boring per client instruction			

Drilling Fluid CLEAR WATER Casing 1.7" Press. Gage Loc. _____
 Ground Water Depth _____ Date _____ Method Det. _____
 Remarks No drill water circulation loss throughout coring operations.

CHART 2-38

FIG. 12

LOGGING NO. 101

LOGGING COMPANY
LOGGING COMPANY
LOGGING COMPANY

PHONE: (314) 201-1111 2000 CALLING SERVICE DR. MARYLAND HEIGHTS, MO. 63043
ST. LOUIS COUNTY

JOB NO. 71-23
CONTRACT NO. 498.4

PROJECT: Lake St. Louis

SOUNDING LOCATION: Sullivan's Extension

DATE	START	END	TIME	DATE	TIME	FROM	TO	CORE RUN	TOTAL	RECOVERY
DEPTH	CLASSIFICATION									
0.0	0.5	Residual Red Clay & Chert Spinel				0.5'	5.5'	5.0'	5.0'	100
0.5	10.0'	Light Green, Hard, Dense Siliceous Material				5.5'	10.5'	5.0'	5.0'	100
		Chert Inclusions				10.5'	15.5'	5.0'	5.0'	100
		Between 21.5 & 23.0' W/5uff Weathered				15.5'	20.5'	5.0'	5.0'	100
		Portions				20.5'	25.5'	5.0'	5.0'	100
						24.5'	29.7'	5.2'	5.2'	100
						29.7'	35.7'	6.0'	6.0'	100
40.0'		Bottom of Boring				35.7'	40.0'	4.3'	4.3'	100

REMARKS: No water level while drilling

[illegible]

501.6

[illegible]

STANDARD
No water loss while drilling.
Drilling 6100 feet below
that passed under 1940.

LOG OF BORING NO. 103

DRILLING COMPANY CO.
 2000 DRILLING SERVICE DR.
 ST. LOUIS COUNTY

PHONE: (314) 291-1111

MARYLAND HEIGHTS, MO. 63043

PROJECT Lake St. Louis

JOB NO. 71-53

BORING LOCATION: Sullivan Section

SURFACE ELEV. 513.8

DEPTH	FROM	TO	CLASSIFICATION	DATE	TIME	CORE RUN		TOTAL RUN	TOTAL RECOVERY	
						FROM	TO		RUN	TOTAL
5.0'	5.0'		Residual Red Clay & Chert Gravel			10.5'	15.0'	4.5'	4.5'	100
5.0'	7.0'		Chert Boulder			15.0'	17.2'	2.2'	2.0'	91
						17.2'	19.1'	1.9'	1.9'	100
						19.1'	25.7'	6.6'	6.6'	100
9.0'	9.0'		Yellow, Soft Shaly Clay Layer			25.7'	27.2'	1.5'	1.5'	100
						27.2'	32.9'	5.7'	5.7'	100
9.0'	10.5'		Weathered, Soft Limestone			32.9'	38.7'	5.8'	5.8'	100
10.5'	13.0'					38.7'	43.7'	5.0'	4.0'	80
			Light Gray Massive Weathered Buff Partings			43.7'	46.0'	2.3'	2.3'	100
			Hard, Dense Limestone with some chert inclusions			46.0'	53.0'	7.0'	7.0'	100
53.0'	53.0'		Bottom of Boring							

REMARKS: No water loss while drilling.

CHART 2-42

LOG OF BORING NO. 122

TROT LUMBER COMPANY CO.

PHONE: (314) 201-1111 2000 DRILLING SERVICE CO. MARYLAND HEIGHTS, MO. 63043
ST. LOUIS COUNTY

PROJECT: Lake St. Louis

USDA NO. 71-63

SURFACE ELEV. 500.0

BORING LOCATION: Mill Creek Section

DATE	START	STOP	TIME	DATE	TIME	DEPTH	CLASSIFICATION	FROM	TO	CORE RUN	TOTAL RUN	RECOVERY
6-11-71	6-11-71	6-15-71	719									
10.0'	10.0'	15.0'	15.0'	15.0'	15.0'	10.0'	Reddish Red Clay & Chert Gravel W/Several	10.0'	15.0'	15.0'	5.0'	3.0'
15.0'	15.0'	16.5'	16.5'	16.5'	16.5'	15.0'	Large Boulders or Stratified Layers of Chert	15.0'	16.5'	16.5'	1.5'	1.0'
16.5'	16.5'	18.0'	18.0'	18.0'	18.0'	16.5'	8 Limestone Below 5.0'	16.5'	18.0'	18.0'	1.5'	1.3'
18.0'	18.0'	20.0'	20.0'	20.0'	20.0'	18.0'	18.0' - 20.0', thin bedded Limestone W/numerous	18.0'	20.0'	20.0'	2.0'	3.0'
20.0'	20.0'	22.5'	22.5'	22.5'	22.5'	20.0'	Clay layers & Chert Inclusions (Chert Fall	20.0'	22.5'	22.5'	2.5'	4.3'
22.5'	22.5'	24.7'	24.7'	24.7'	24.7'	22.5'	In From Seams Caused Core Grinding	22.5'	24.7'	24.7'	2.2'	1.7'
24.7'	24.7'						Lost Diamond Bit in Hole -					
							Sharp Chert Cut off Outer					
							Partial					
34.7'	34.7'						Bottom of Boring					

REMARKS: No water loss during drilling.

CHART 2-43

SECRET

PHONE: (314) 291-1111
2500 DRILLING SERVICE DR.
MARYLAND HEIGHTS, MO. 63043
ST. LOUIS COUNTY

[illegible]

10312. 71-62

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

501.2

15-00000

719
2:3:

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525

[illegible]

101
102
103
104

COEF RUN	TOTAL	RECOVERY
1	1	1
2	2	2
3	3	3
4	4	4
5	5	5
6	6	6
7	7	7
8	8	8
9	9	9
10	10	10
11	11	11
12	12	12
13	13	13
14	14	14
15	15	15
16	16	16
17	17	17
18	18	18
19	19	19
20	20	20
21	21	21
22	22	22
23	23	23
24	24	24
25	25	25
26	26	26
27	27	27
28	28	28
29	29	29
30	30	30
31	31	31
32	32	32
33	33	33
34	34	34
35	35	35
36	36	36
37	37	37
38	38	38
39	39	39
40	40	40
41	41	41
42	42	42
43	43	43
44	44	44
45	45	45
46	46	46
47	47	47
48	48	48
49	49	49
50	50	50
51	51	51
52	52	52
53	53	53
54	54	54
55	55	55
56	56	56
57	57	57
58	58	58
59	59	59
60	60	60
61	61	61
62	62	62
63	63	63
64	64	64
65	65	65
66	66	66
67	67	67
68	68	68
69	69	69
70	70	70
71	71	71
72	72	72
73	73	73
74	74	74
75	75	75
76	76	76
77	77	77
78	78	78
79	79	79
80	80	80
81	81	81
82	82	82
83	83	83
84	84	84
85	85	85
86	86	86
87	87	87
88	88	88
89	89	89
90	90	90
91	91	91
92	92	92
93	93	93
94	94	94
95	95	95
96	96	96
97	97	97
98	98	98
99	99	99
100	100	100

Ω
1-

1. The first step is to identify the problem or goal. This involves understanding the current situation and what needs to be achieved.

43
42
41
40
39
38
37
36
35
34
33
32
31
30
29
28
27
26
25
24
23
22
21
20
19
18
17
16
15
14
13
12
11
10
9
8
7
6
5
4
3
2
1

Exhausted Below 3.0'

[illegible]

✓ Approved Check facilities

For a detailed analysis of the data, see the following table:

U
:
(
.
:
:
:
:

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

Submitted
William D. King Sr., 2023-01-01

PHONE: (314) 291-1111
2500 DRILLING SERVICE DR.
MARYLAND HEIGHTS, MO. 63043
ST. LOUIS COUNTY

5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
841
842
843

10310. — 1765.

THE UNIVERSITY OF CHICAGO

506.8

١٠٠

[illegible]

REMARKS:

[illegible]

THE UNIVERSITY OF CHICAGO

LOGS OF BORINGS NO. 105

7207 DRILLING COMPANY, INC.

PHONE: (314) 291-1111 2500 DRILLING SERVICE DR. MARYLAND HEIGHTS, MO. 63043
ST. LOUIS COUNTY

PROJECT Lake St. Louis

LOG NO. 71-63

BORING LOCATION Shellman Section

CORRECTION 514.4

DATE		START	(1941)	RIG	CORERUN		TOTAL	RECOVERY	
DEPTH		CLASSIFICATION		DATE	TIME	FROM	TO	TOTAL	%
FROM	TO							RUN	
0.0	5.0	unconsolidated brown silty sand				9.2'	14.2'	5.0'	100
5.0	53.0'	light gray. hard, dense.				17.0'	22.0'	5.0'	100
		limestone w/numerous chert				19.0'	23.0'	4.0'	100
		inclusions				23.0'	28.0'	5.0'	100
						28.0'	33.0'	5.0'	100
						33.0'	38.0'	5.0'	100
						38.0'	43.0'	5.0'	100
						43.0'	48.0'	5.0'	100
						48.0'	53.0'	5.0'	100
						53.0'	58.0'	5.0'	100
						58.0'	63.0'	5.0'	100
						63.0'	68.0'	5.0'	100
						68.0'	73.0'	5.0'	100
						73.0'	78.0'	5.0'	100
						78.0'	83.0'	5.0'	100
						83.0'	88.0'	5.0'	100
						88.0'	93.0'	5.0'	100
						93.0'	98.0'	5.0'	100
						98.0'	103.0'	5.0'	100
						103.0'	108.0'	5.0'	100
						108.0'	113.0'	5.0'	100
						113.0'	118.0'	5.0'	100
						118.0'	123.0'	5.0'	100
						123.0'	128.0'	5.0'	100
						128.0'	133.0'	5.0'	100
						133.0'	138.0'	5.0'	100
						138.0'	143.0'	5.0'	100
						143.0'	148.0'	5.0'	100
						148.0'	153.0'	5.0'	100
						153.0'	158.0'	5.0'	100
						158.0'	163.0'	5.0'	100
						163.0'	168.0'	5.0'	100
						168.0'	173.0'	5.0'	100
						173.0'	178.0'	5.0'	100
						178.0'	183.0'	5.0'	100
						183.0'	188.0'	5.0'	100
						188.0'	193.0'	5.0'	100
						193.0'	198.0'	5.0'	100
						198.0'	203.0'	5.0'	100
						203.0'	208.0'	5.0'	100
						208.0'	213.0'	5.0'	100
						213.0'	218.0'	5.0'	100
						218.0'	223.0'	5.0'	100
						223.0'	228.0'	5.0'	100
						228.0'	233.0'	5.0'	100
						233.0'	238.0'	5.0'	100
						238.0'	243.0'	5.0'	100
						243.0'	248.0'	5.0'	100
						248.0'	253.0'	5.0'	100
						253.0'	258.0'	5.0'	100
						258.0'	263.0'	5.0'	100
						263.0'	268.0'	5.0'	100
						268.0'	273.0'	5.0'	100
						273.0'	278.0'	5.0'	100
						278.0'	283.0'	5.0'	100
						283.0'	288.0'	5.0'	100
						288.0'	293.0'	5.0'	100
						293.0'	298.0'	5.0'	100
						298.0'	303.0'	5.0'	100
						303.0'	308.0'	5.0'	100
						308.0'	313.0'	5.0'	100
						313.0'	318.0'	5.0'	100
						318.0'	323.0'	5.0'	100
						323.0'	328.0'	5.0'	100
						328.0'	333.0'	5.0'	100
						333.0'	338.0'	5.0'	100
						338.0'	343.0'	5.0'	100
						343.0'	348.0'	5.0'	100
						348.0'	353.0'	5.0'	100
						353.0'	358.0'	5.0'	100
						358.0'	363.0'	5.0'	100
						363.0'	368.0'	5.0'	100
						368.0'	373.0'	5.0'	100
						373.0'	378.0'	5.0'	100
						378.0'	383.0'	5.0'	100
						383.0'	388.0'	5.0'	100
						388.0'	393.0'	5.0'	100
						393.0'	398.0'	5.0'	100
						398.0'	403.0'	5.0'	100
						403.0'	408.0'	5.0'	100
						408.0'	413.0'	5.0'	100
						413.0'	418.0'	5.0'	100
						418.0'	423.0'	5.0'	100
						423.0'	428.0'	5.0'	100
						428.0'	433.0'	5.0'	100
						433.0'	438.0'	5.0'	100
						438.0'	443.0'	5.0'	100
						443.0'	448.0'	5.0'	100
						448.0'	453.0'	5.0'	100
						453.0'	458.0'	5.0'	100
						458.0'	463.0'	5.0'	100
						463.0'	468.0'	5.0'	100
						468.0'	473.0'	5.0'	100
						473.0'	478.0'	5.0'	100
						478.0'	483.0'	5.0'	100
						483.0'	488.0'	5.0'	100
						488.0'	493.0'	5.0'	100
						493.0'	498.0'	5.0'	100
						498.0'	503.0'	5.0'	100
						503.0'	508.0'	5.0'	100
						508.0'	513.0'	5.0'	100
						513.0'	518.0'	5.0'	100
						518.0'	523.0'	5.0'	100
						523.0'	528.0'	5.0'	100
						528.0'	533.0'	5.0'	100
						533.0'	538.0'	5.0'	100
						538.0'	543.0'	5.0'	100
						543.0'	548.0'	5.0'	100
						548.0'	553.0'	5.0'	100
						553.0'	558.0'	5.0'	100
						558.0'	563.0'	5.0'	100
						563.0'	568.0'	5.0'	100
						568.0'	573.0'	5.0'	100
						573.0'	578.0'	5.0'	100
						578.0'	583.0'	5.0'	100
						583.0'	588.0'	5.0'	100
						588.0'	593.0'	5.0'	100
						593.0'	598.0'	5.0'	100
						598.0'	603.0'	5.0'	100
						603.0'	608.0'	5.0'	100
						608.0'	613.0'	5.0'	100
						613.0'	618.0'	5.0'	100
						618.0'	623.0'	5.0'	100
						623.0'	628.0'	5.0'	100
						628.0'	633.0'	5.0'	100
						633.0'	638.0'	5.0'	100
						638.0'	643.0'	5.0'	100
						643.0'	648.0'	5.0'	100
						648.0'	653.0'	5.0'	100
						653.0'	658.0'	5.0'	100
						658.0'	663.0'	5.0'	100
						663.0'	668.0'	5.0'	100
						668.0'	673.0'	5.0'	100
						673.0'	678.0'	5.0'	100
						678.0'	683.0'	5.0'	100
						683.0'	688.0'	5.0'	100
						688.0'	693.0'	5.0'	100
						693.0'	698.0'	5.0'	100
						698.0'	703.0'	5.0'	100
						703.0'	708.0'	5.0'	100
						708.0'	713.0'	5.0'	100
						713.0'	718.0'	5.0'	100
						718.0'	723.0'	5.0'	100
						723.0'	728.0'	5.0'	100
						728.0'	733.0'	5.0'	100
						733.0'	738.0'	5.0'	100
						738.0'	743.0'	5.0'	100
						743.0'	748.0'	5.0'	100
						748.0'	753.0'	5.0'	100
						753.0'	758.0'	5.0'	100
						758.0'	763.0'	5.0'	100
						763.0'	768.0'	5.0'	100
						768.0'	773.0'	5.0'	100
						773.0'	778.0'	5.0'	100
						778.0'	783.0'	5.0'	100
						783.0'	788.0'	5.0'	100
						788.0'	793.0'	5.0'	100
						793.0'	798.0'	5.0'	100
						798.0'	803.0'	5.0'	100
						803.0'	808.0'	5.0'	100
						808.0'	813.0'	5.0'	100
						813.0'	818.0'	5.0'	100
						818.0'	823.0'	5.0'	100
						823.0'	828.0'	5.0'	100
						828.0'	833.0'	5.0'	100
						833.0'	838.0'	5.0'	100
						838.0'	843.0'	5.0'	100
						843.0'	848.0'	5.0'	100
						848.0'	853.0'	5.0'	100
						853.0'	858.0'	5.0'	100
						858.0'	863.0'	5.0'	100
						863.0'	868.0'	5.0'	100
						868.0'	873.0'	5.0'	100
						873.0'	878.0'		

LOG CLOSING NO. 100

ST. LOUIS COUNTY
 PHONE: (314) 291-1111
 2500 DRILLING SERVICE DR.
 ST. LOUIS COUNTY

MARYLAND HEIGHTS, MO. 63043

PROJECT Lake St. Louis

LOG NO. 71-62

SINKING LOCATION 5-111111-00000

SURFACE EL. 506.0

DATE: 6-22-71 (FINISH) 6-22-71

INSTRUMENT

DEPTH FROM TO	CLASSIFICATION	DATE	TIME	CORE RUN		TOTAL RUN	RECOVERY TOTAL	RECOVERY %
				FROM	TO			
0.0	RESIDUAL RED CLAY & CHERT GRAVEL			10.8'	13.5'	3.0'	0.0'	7
	W/ Boulders and cobbles			14.0'	15.2'	1.2'	1.2'	100
	SECTION 4.5'			15.2'	19.1'	3.9'	3.9'	100
5.0	BRICKEN LIMESTONE & CHERT			19.1'	23.1'	5.0'	5.0'	100
				23.1'	29.1'	5.0'	5.0'	100
10.0	Light Gray, Hard, Dense, Limestone, w/ numerous chert inclusions			29.1'	33.1'	5.0'	5.0'	100
				33.1'	39.1'	5.0'	5.0'	100
				39.1'	43.1'	5.0'	5.0'	100
15.0	Bottom of casing			43.1'	45.0'	1.9'	1.9'	100

REMARKS: Set casing at 10'16" cased to 10'16" - chert, no recovery, pulled casing.

ramped to 14', reset casing.

No water loss while drilling - water at 16' after 15 hours.

CHART 2-48

()
()
()
()
()
()
()
()
()
()
()

PHONE: (314) 231-1111
2000 DRILLING SERVICE DR.
MARYLAND HEIGHTS, MO. 63043
ST. LOUIS COUNTY

SECRET

~~CONFIDENTIAL~~ - 1 - 62

SECRET

7.075 520.2

7-27-65

616

REFLECTOR:

[illegible]

REMARKS:

[illegible]

LOGGING NO. 112

COLUMBIA UNIVERSITY

PHONE: (314) 231-1111 2000 BILLING SERVICE DR. MARYLAND HEIGHTS, MO. 63043
ST. LOUIS COUNTY

PROJECT 213 St. Louis

LOG NO. 71-63

CORE LOCATION

SURFACE 5276

DATE 12-1-71

PERIOD 7-5-71

RIS 119

INSPECTOR

DEPTH FROM TO	CLASSIFICATION	DATE	TIME	CORE RUN		TOTAL RUN	TOTAL RECOVERY
				FROM	TO		
0.0	RESIDUE RED GRAY & WHITE GRAVEL			10.0'	15.0'	5.0'	3.7'
5.0	INTERBEDded GRAY Limestone			15.0'	19.7'	4.7'	3.5'
10.0	INTERBEDded RED GRAY SANDS			19.7'	22.8'	3.1'	3.0'
15.0	Light Gray, med. Tanes			22.8'	26.2'	3.4'	2.5'
20.0	Limestone w/ many nodules			26.2'	29.2'	3.0'	3.0'
25.0	Chert nodules			29.2'	39.2'	10.0'	10.0'
30.0	Gray nodules water			39.2'	41.9'	2.7'	2.7'
35.0	Weathered Blue Limestone Horizons			41.9'	51.9'	10.0'	9.5'
40.0	Light Gray, med. Tanes			51.9'	55.9'	4.0'	2.0'
45.0	Limestone w/ numerous			55.9'	60.0'	4.0'	3.0'
50.0	Chert nodules			60.0'	60.0'	0.0'	0.0'
55.0	Bottom of boring						

REMARKS: No water loss while drilling. Water at 60' at completion.

Core Grinding Due to Chert Fall In

CHART 2-50

PHONE: (314) 251-1111
FAX: (314) 251-1111
ADDRESS: 1000 N. GARDEN ST., ST. LOUIS, MO 63102
E-MAIL: info@stlouiscity.org

PHONE: (314) 291-1111
2000 MILLING SERVICE DR.
ST. LOUIS COUNTY
MARYLAND HEIGHTS, MO. 63043

100

0.0000

5298

[illegible][illegible]

FEEL ARIS: "A nation's future is in the hands of its children"

CHART 2-51

LOG OF BORING NO. 116

TEST DRILLING COMPANY CO.
DRILLING SERVICE DR.
 2500 CHILLING SERVICE DR.
 ST. LOUIS COUNTY

PHONE: (314) 291-1111

MARYLAND HEIGHTS, MO. 63043

PROJECT: 24th St., Louis

JOB NO. 71-63

BORING LOCATION: 24th St., Louis

DATE: 5/2/9

INSTRUCTIONS:

TIME

DATE

(FINISH) 5-24-71

(START) 5-23-71

DEPTH FT.	TO	CLASSIFICATION	TIME	DATE	CORE RUN		TOTAL	RECOVERY
					FROM	TO	RUN	TOTAL
0.0	5.0	Reddish-brown clay, silty, sandy			10.5'	12.3'	1.8'	1.8'
5.0	10.5	Reddish-brown clay, silty, sandy			12.3'	17.3'	5.0'	5.0'
		Reddish-brown clay, silty, sandy			17.3'	22.3'	5.0'	5.0'
10.5	15.0	Light Gray, Hard, Dense			22.3'	27.3'	5.0'	5.0'
		Light Gray w/ numerous			27.3'	32.3'	5.0'	5.0'
		Chert Inclusions			32.3'	37.3'	5.0'	5.0'
15.0	20.0	Bottom of Boring			37.3'	42.3'	5.0'	5.0'
					42.3'	47.3'	5.0'	5.0'
					47.3'	52.3'	5.0'	5.0'
					52.3'	57.3'	5.0'	5.0'
					57.3'	62.3'	5.0'	5.0'
					62.3'	67.3'	5.0'	5.0'
					67.3'	72.3'	5.0'	5.0'
					72.3'	77.3'	5.0'	5.0'
					77.3'	82.3'	5.0'	5.0'
					82.3'	87.3'	5.0'	5.0'
					87.3'	92.3'	5.0'	5.0'
					92.3'	97.3'	5.0'	5.0'
					97.3'	102.3'	5.0'	5.0'
					102.3'	107.3'	5.0'	5.0'
					107.3'	112.3'	5.0'	5.0'
					112.3'	117.3'	5.0'	5.0'
					117.3'	122.3'	5.0'	5.0'
					122.3'	127.3'	5.0'	5.0'
					127.3'	132.3'	5.0'	5.0'
					132.3'	137.3'	5.0'	5.0'
					137.3'	142.3'	5.0'	5.0'
					142.3'	147.3'	5.0'	5.0'
					147.3'	152.3'	5.0'	5.0'
					152.3'	157.3'	5.0'	5.0'
					157.3'	162.3'	5.0'	5.0'
					162.3'	167.3'	5.0'	5.0'
					167.3'	172.3'	5.0'	5.0'
					172.3'	177.3'	5.0'	5.0'
					177.3'	182.3'	5.0'	5.0'
					182.3'	187.3'	5.0'	5.0'
					187.3'	192.3'	5.0'	5.0'
					192.3'	197.3'	5.0'	5.0'
					197.3'	202.3'	5.0'	5.0'
					202.3'	207.3'	5.0'	5.0'
					207.3'	212.3'	5.0'	5.0'
					212.3'	217.3'	5.0'	5.0'
					217.3'	222.3'	5.0'	5.0'
					222.3'	227.3'	5.0'	5.0'
					227.3'	232.3'	5.0'	5.0'
					232.3'	237.3'	5.0'	5.0'
					237.3'	242.3'	5.0'	5.0'
					242.3'	247.3'	5.0'	5.0'
					247.3'	252.3'	5.0'	5.0'
					252.3'	257.3'	5.0'	5.0'
					257.3'	262.3'	5.0'	5.0'
					262.3'	267.3'	5.0'	5.0'
					267.3'	272.3'	5.0'	5.0'
					272.3'	277.3'	5.0'	5.0'
					277.3'	282.3'	5.0'	5.0'
					282.3'	287.3'	5.0'	5.0'
					287.3'	292.3'	5.0'	5.0'
					292.3'	297.3'	5.0'	5.0'
					297.3'	302.3'	5.0'	5.0'
					302.3'	307.3'	5.0'	5.0'
					307.3'	312.3'	5.0'	5.0'
					312.3'	317.3'	5.0'	5.0'
					317.3'	322.3'	5.0'	5.0'
					322.3'	327.3'	5.0'	5.0'
					327.3'	332.3'	5.0'	5.0'
					332.3'	337.3'	5.0'	5.0'
					337.3'	342.3'	5.0'	5.0'
					342.3'	347.3'	5.0'	5.0'
					347.3'	352.3'	5.0'	5.0'
					352.3'	357.3'	5.0'	5.0'
					357.3'	362.3'	5.0'	5.0'
					362.3'	367.3'	5.0'	5.0'
					367.3'	372.3'	5.0'	5.0'
					372.3'	377.3'	5.0'	5.0'
					377.3'	382.3'	5.0'	5.0'
					382.3'	387.3'	5.0'	5.0'
					387.3'	392.3'	5.0'	5.0'
					392.3'	397.3'	5.0'	5.0'
					397.3'	402.3'	5.0'	5.0'
					402.3'	407.3'	5.0'	5.0'
					407.3'	412.3'	5.0'	5.0'
					412.3'	417.3'	5.0'	5.0'
					417.3'	422.3'	5.0'	5.0'
					422.3'	427.3'	5.0'	5.0'
					427.3'	432.3'	5.0'	5.0'
					432.3'	437.3'	5.0'	5.0'
					437.3'	442.3'	5.0'	5.0'
					442.3'	447.3'	5.0'	5.0'
					447.3'	452.3'	5.0'	5.0'
					452.3'	457.3'	5.0'	5.0'
					457.3'	462.3'	5.0'	5.0'
					462.3'	467.3'	5.0'	5.0'
					467.3'	472.3'	5.0'	5.0'
					472.3'	477.3'	5.0'	5.0'
					477.3'	482.3'	5.0'	5.0'
					482.3'	487.3'	5.0'	5.0'
					487.3'	492.3'	5.0'	5.0'
					492.3'	497.3'	5.0'	5.0'
					497.3'	502.3'	5.0'	5.0'
					502.3'	507.3'	5.0'	5.0'
					507.3'	512.3'	5.0'	5.0'
					512.3'	517.3'	5.0'	5.0'
					517.3'	522.3'	5.0'	5.0'
					522.3'	527.3'	5.0'	5.0'
					527.3'	532.3'	5.0'	5.0'
					532.3'	537.3'	5.0'	5.0'
					537.3'	542.3'	5.0'	5.0'
					542.3'	547.3'	5.0'	5.0'
					547.3'	552.3'	5.0'	5.0'
					552.3'	557.3'	5.0'	5.0'
					557.3'	562.3'	5.0'	5.0'
					562.3'	567.3'	5.0'	5.0'
					567.3'	572.3'	5.0'	5.0'
					572.3'	577.3'	5.0'	5.0'
					577.3'	582.3'	5.0'	5.0'
					582.3'	587.3'	5.0'	5.0'
					587.3'	592.3'	5.0'	5.0'
					592.3'	597.3'	5.0'	5.0'
					597.3'	602.3'	5.0'	5.0'
					602.3'	607.3'	5.0'	5.0'
					607.3'	612.3'	5.0'	5.0'
					612.3'	617.3'	5.0'	5.0'
					617.3'	622.3'	5.0'	5.0'
					622.3'	627.3'	5.0'	5.0'
					627.3'	632.3'	5.0'	5.0'
					632.3'	637.3'	5.0'	5.0'
					637.3'	642.3'	5.0'	5.0'
					642.3'	647.3'	5.0'	5.0'
					647.3'	652.3'	5.0'	5.0'
					652.3'	657.3'	5.0'	5.0'
					657.3'	662.3'	5.0'	5.0'
					662.3'	667.3'	5.0'	5.0'
					667.3'	672.3'	5.0'	5.0'
					672.3'	677.3'	5.0'	5.0'
					677.3'	682.3'	5.0'	5.0'
					682.3'	687.3'	5.0'	5.0'
					687.3'	692.3'	5.0'	5.0'
					692.3'	697.3'	5.0'	5.0'
					697.3'	702.3'	5.0'	5.0'
					702.3'	707.3'	5.0'	5.0'
					707.3'	712.3'	5.0'	5.0'
					712.3'	717.3'	5.0'	5.0'
					717.3'	722.3'	5.0'	5.0'
					722.3'	727.3'	5.0'	5.0'
					727.3'	732.3'	5.0'	5.0'
					732.3'	737.3'	5.0'	5.0'
					737.3'	742.3'	5.0'	5.0'
					742.3'	747.3'	5.0'	5.0'
					747.3'	752.3'	5.0'	5.0'
					752.3'	757.3'	5.0'	5.0'
					757.3'	762.3'	5.0'	5.0'
					762.3'	767.3'	5.0'	5.0'
					767.3'	772.3'	5.0'	5.0'
					772.3'	777.3'	5.0'	5.0'
					777.3'	782.3'	5.0'	5.0'
					782.3'	787.3'	5.0'	5.0'
					787.3'	792.3'	5.0'	5.0'
					792.3'	797.3'	5.0'	5.0'
					797.3'	802.3'	5.0'	5.0'
					802.3'	807.3'	5.0'	5.0'
					807.3'	812.3'	5.0'	5.0'
					812.3'	817.3'	5.0'	5.0'
					817.3'	822.3'	5.0'	5.0'
					822.3'	827.3'	5.0'	5.0'
					827.3'	832.3'	5.0'	5.0'
					832.3'	837.3'	5.0'	5.0'
					837.3'	842.3'	5.0'	5.0'
					842.3'	847.3'	5.0'	5.0'
					847.3'	852.3'	5.0'	5.0'
					852.3'	857.3'	5.0'	5.0'
					857.3'	862.3'	5.0'	5.0'
					862.3'	867.3'	5.0'	5.0'
					867.3'	872.3'	5.0'	5.0'
					872.3'	877.3'	5.0'	5.0'
					877.3'	882.3'	5.0'	5.0'
					882.3'	887.3'	5.0'	5.0'
					887.3'	892.3'	5.0'	5.0'
					892.3'	897.3'	5.0'	5.0'
					897.3'	902.3'	5.0'	5.0'
					902.3'	907.3'	5.0'	5.0'
					907.3'	912.3'	5.0'	5.0'
					912.3'	917.3'	5.0'	5.0'
					917.3'	922.3'	5.0'	5.0'
					922.3'	927.3'	5.0'	5.0'
					927.3'	932.3'	5.0'	5.0'
					932.3'	937.3'	5.0'	5.0'

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525

PHONE: (314) 231-1111
2000 DRILLING SERVICE DR.
MARYLAND HEIGHTS, MO. 63043
ST. LOUIS COUNTY

PROJECT: 100-64-1000
 DATE: 10-1-68
 BY: 5916
 100-64-1000

0547

DEPTH	CLASSIFICATION	DATE	TIME	CORE RUN		TOTAL RUN	RECOVERY
				FROM	TO		
12.0'				12.0'	15.5'	3.5'	3.5' 100
13.0'	Bedded Red Clay & Shale, normal			13.5'	16.7'	1.2'	0.7' 59
14.0'	Bedded Reddish Cherty Limestone			16.7'	17.7'	1.0'	1.0' 100
	W/ numerous clay seams & thin thin			17.7'	24.5'	6.8'	2.3' 34
	Open seams			24.5'	25.5'	1.0'	1.0' 100
	Rock some drilling classification						
12.0' 24.0	Light Gray to Buff, thin			25.5'	29.2'	3.7'	3.7' 100
	Bedded Cherty Limestone			29.2'	39.2'	10.0'	10.0' 100
	W/ numerous clay seams			39.2'	49.2'	10.0'	10.0' 100
12.0' 55.0'	Light Gray, hard, dense, limestone			49.2'	55.0'	5.8'	5.8' 100
	W/ numerous clay inclusions						
55.0'	Bottom of boring						

REMARKS:

CHART 2-53

[illegible]

PHONE: (314) 231-1111 2000 DRILLING SERVICE DR. MARYLAND HEIGHTS, MO. 63043
ST. LOUIS COUNTY

[illegible]

77-13

F

542.0

p. 6: 719

TX-6-1 (continued)

11-11-11

DEPTH		CLASSIFICATION	DATE	TIME	CORE RUN		TOTAL RUN	RECOVERY
FROM	TO				FROM	TO		
0.0	10.0	Reddish Red Clay & Shale Gravel			10.01	10.51	2.51	1.01
		" / Sand, Gravel & Boulder			10.51	22.21	2.71	1.01
10.0	20.01	Weathered Broken Limestone			20.01	23.71	1.51	1.01
		8' Shale w/ thinning clay			23.71	25.01	2.31	2.01
		Layers - No water circulation loss			25.01	26.51	2.51	1.01
					26.51	30.21	1.71	0.11
					30.01	33.01	2.51	0.51
					33.01	34.51	1.51	0.11
					34.51	38.71	5.01	5.01
					38.71	40.71	2.01	2.01
					40.71	42.71	2.01	2.01
					42.71	45.71	3.01	2.01
					45.71	49.01	3.51	1.51
					49.01	50.01	1.01	1.01

STANDARD

17.0' - 30.0' Light Gray to Buff thin bedded Cherty Limestone

10/17/74 comes - Case continuing due to phone call in

10-27-10-28

...

*Ira Nathan
Danny*

GEOLOGIC INVESTIGATION OF PROPOSED LAKE SITE ON PERUQUE CREEK
ST. CHARLES COUNTY

The proposed lake site on Peruque Creek with a dam located in the center of sec. 26, T. 47 N., R. 2 E., will impound waters in a region of limestone bedrock. Rock exposures are soil covered for the most part except for the slopes at the dam site. The thin veneer of soil and rock fragments on the abutments indicates that the earthen fill must be keyed into bedrock.

The limestone bedrock, referred to as the Burlington formation, is firm, massive, and contains a high percentage of chert. The Burlington normally is fissured and open to some extent. The several springs present within the lake area verify this generality. As is customary with limestone bedrock, suitable precautions are necessary so that impounded lake waters are not lost through openings in the limestone. Therefore, the springs which will be in the lower part of the lake such as the spring in the NW $\frac{1}{4}$ SW $\frac{1}{4}$ SE $\frac{1}{4}$ sec. 26, T. 47 N., R. 2 E., should be cleaned of loose rock and soil debris and then padded. The padding should consist of compacted coarse rock covered by two feet of relatively impermeable clay. The lake will probably not have sufficient hydrostatic pressure to reverse the springs, and the failure to pad all the springs should have no adverse affects. However, springs near the dam site, such as the above mentioned outlet should be covered. Springs at or slightly below the water line need not be disturbed.

The rock abutments will consist of firm limestone bedrock except for a several foot thick surficial covering of loose and open layered rock. Therefore, the core trench must be excavated into

each abutment a sufficient depth so that the clay core can be compacted against firm rock. This may increase construction costs, but failure to key the earthen core into firm rock on the abutments can result in high water loss and possible instability of the earthen dam.

An excavated rock core trench may not be necessary along the base of the earthen dam. If sufficient relatively tight alluvial material and compacted clay padding cover the present stream channel are extended upstream from the base of the dam, then there will be a limited possibility of water loss along the base of the dam. However, all loose rock material should be cleaned from the bottom of the core trench so that the clay core can be compacted on firm bedrock. If bedrock is at excessive depth then it may be necessary to bottom the core trench on suitable alluvial soil.

An earthen structure of the size contemplated for Peruque Creek should not be undertaken without a thorough knowledge as to the character of the rock. Surface exposures give only a partial indication as to the water tightness of the bedrock. Therefore, additional information as to possible water loss should be obtained by core drilling and pressure testing. Each abutment should be cored and pressure tested with the holes located at the approximate elevation of the pool level. The holes should be deepened to the average level of bedrock surface in the Peruque Valley floodplain. A third hole located along the center line should be covered and pressure tested at least 10 feet into solid rock. If these holes indicate that the rock is open and water loss is excessive, then additional holes will be needed to determine the seriousness of the adverse rock characteristics. Since the lake is not planned

to be excessively deep, the core hole exploration would not be necessary if borrow areas were located near or above water level. However, the need to obtain most of the borrow from the floodplain indicates that the bedrock should be relatively watertight. Some water loss can be tolerated with the high drainage to lake ratios, but if many open caves are noted in the drilling program, then it will be necessary to leave much of the floodplain soil deposits in place. Borrow will have to be obtained at or above water line.

The most apparent construction problem of the lake site may be core trench excavation in the valley alluvium. The floodplain sediments at Peruque Creek may flood much of the earthen excavation. The problem may exist in some borrow areas also. The general groundwater level appears to be at or above floodplain level and this will tend to recharge the alluvium of the floodplain. Therefore, adequate auger exploration should also be accomplished with particular attention given to the water table level in the floodplain. Over all features of the lake site indicate that it is well situated from the geologic aspect. No major hazards were apparent. However, the relatively simple additional exploration should not be ignored when construction of lakes and dams of this magnitude are considered.

James H. Williams
Engineering Geologist
Missouri Geological Survey
February 21, 1963

Eng. Sect.
llh

GEOLOGIC REPORT ON THE ST. LOUIS LAKE (BROWNING), ST. CHARLES COUNTY

The proposed lake site is located in the SW $\frac{1}{4}$ NW $\frac{1}{4}$ SE $\frac{1}{4}$ sec. 27, T.47 N., R.2 E. (Troy Quad.). Geologically the location is excellent for water impoundment. The bedrock formation, Keokuk Limestone, is present in the valley area but crops out in very few exposures along the steeper portions of the valley slopes. The Keokuk has limestone beds that are thin to medium in thickness (4" to 2') and interlayered with persistent thick nodules of chert that are in 2" to 6" beds. Most of the valley is covered by a thick mantle of silty clay mixed with chert fragments.

While geologically the area is suitable and there are no major hazards, particular attention must be given to the abutments and valley floor at the dam site. Weathered bedrock exposed near the abutments indicate that seepage could occur along horizontal openings if these are not intercepted by the core trench. Location of the centerline so that small side valley draws can be utilized as part of the abutment core trench will facilitate excavation into fresh unweathered bedrock. Similarly excavation along the floor of the valley should be carried through the weathered bedrock zone. The bedrock excavation may require the use of a rear mounted ripper. It is most important that all weathered bedrock layers in the core be removed even if it should require some drilling and blasting.

During the field examination it was considered that the dam site should be shifted upstream so that the side valley draws could be utilized. This upstream relocation also placed the dam on a more shallow thickness of alluvium than at the originally proposed downstream site. This will further enhance the suitability of the site since it will be easier to complete the core trench excavations. Greater thickness of alluvium such as the downstream site generally involve the problems of more permeable zones consisting of gravels and boulders.

Since subsurface exploration has outlined the nature of the subsoil and bedrock so that major seepage hazards have been noted and a positive cutoff core is planned borrow may be obtained from areas most convenient from an engineering design viewpoint.

James H. Williams
Chief, Eng. Geol. Section
Missouri Geological Survey
September 30, 1966

Eng. Geol.
Division

ADDENDUM TO GEOLOGIC REPORT ON LAKE ST. LOUIS, ST. CHARLES COUNTY

Preliminary seismic exploration in the valley of Perdue Creek indicates that depth to bedrock varies from about 20 feet to at least 32 feet. On the right portion of the valley floodplain, it appears that alluvial silt loam with normal soil moisture has a thickness of 20 to 23 feet. The alluvium is underlain by dense firm limestones consisting of the Keokuk Formation. Toward the center of the valley it appears that about 12 to 16 feet of moist silt loam is underlain by a 12 to 16 foot layer of water saturated sands and gravels. This is in turn underlain at a depth of 30 to 32 feet by limestone. There is no evidence that the limestone surface is extremely pinnacled although it would not be unusual to find variations in relief of 5 to 8 feet in this type of bedrock. However, from a general indication of the type of erosion common to a stream of this size and the preliminary studies by the seismic it would appear that the bedrock surface across the valley floor is relatively uniform.

Velocities in the limestone indicate that it is firm and fresh material. The limestone does not appear to have major caves or extensive soft weathered zones.

The seismic data only outlines the major features of the valley. Subsurface drilling of the bedrock and possible pressure testing are needed to more accurately outline valley conditions.

James H. Williams
Chief, Eng. Geol. Section
Missouri Geological Survey
June 6, 1967

4 64
ADDENDUM TO LAKE ST. LOUIS, ST. CHARLES COUNTY

Several geologic examinations were made during the work in the core trench. The core for the dam is being completed so that leakage or stability problems associated with geologic features will not affect the dam or lake.

The present plans to investigate in detail the foundation in the area of a spring by drilling, dye studies, and possibly geophysical reconnaissance will provide adequate geological information as to the foundation characteristics near this spring.

The spring flows from a limestone crevice, and is considered to have a bedrock source that is not connected with Peruque Creek. Water temperature of the spring measured on 15 April 1969 was 51°F. Water temperature of Peruque was 63°. The 51°F temperature indicates that warm water contamination is not associated with the spring source. Additional temperature measurements and dye studies should be made for comparison.

Plans to cut off the spring water flow by grouting are those techniques that are customarily used for sealing off water movement in bedrock crevices. This will be a matter of several bore holes in the water loss area followed by emplacement of the grout.


The localized water loss from Peruque Creek channel into the core trench is not considered to be related to the major source of water coming from this limestone fissure. It is thought that the stream channel loss followed along a more deeply weathered surface of the bedrock. Dewatering of the alluvium and the core trench led to the surface alluvial sinks. Such a phenomena is not unusual when dewatering changes the foundation characteristics of alluvium.

James H. Williams
Chief, Eng. Geol. Section
Missouri Geological Survey
May 12, 1969

APPENDIX



NO. 1: PLACING EARTH FILL AT DAM



NO. 2: SHEET PILE CUTOFF AT DAM




NO. 3: SPILLWAY - STA. 1+72 TO STA. 2+92



NO. 4: CHANNEL - STA. 9+00 TO STA. 12+00



NO. 5: CURING SPILLWAY MONOLITHS




NO. 6: NORMAL POOL SPILLWAY SECTION




NO. 7: CLEANING CAVITY IN SPILLWAY FOUNDATION - STA. 5+75+



NO. 8: SPILLWAY FOUNDATION - STA. 5+56 TO STA. 5+89




NO. 9: SPILLWAY MONOLITH - STA. 1+24 TO STA. 1+48



NO. 10: SPILLWAY TIE-IN AT DAM



NO. 11: UPSTREAM FACE OF DAM



NO. 12: DOWNSTREAM FACE OF DAM



NO. 13: 72" LAKE DRAWDOWN PIPE



NO. 14: SEWAGE LIFT STATION



NO. 15: I-70 BRIDGES FROM DAM CREST



NO. 16: OUTLET CHANNEL FROM DAM CREST




NO. 17: UPSTREAM END OUTLET CHANNEL



NO. 18: CHANNEL BANK - STA. 12+40₊



NO. 19: SPILLWAY, NOTE 3-8" PIPES



NO. 20: OUTLET CHANNEL BELOW DAM



NO. 21: HIGHWAY 40-61 BRIDGE



NO. 22: DOWNSTREAM FACE LAKE SAINT LOUISE DAM

HYDROLOGIC COMPUTATIONS

1. Triangular unit hydrographs and the Soil Conservation Service method of runoff determination as described in the Bureau of Reclamation publication "Design of Small Dams" were used to develop the inflow hydrographs (see Plate 16) with hydrologic inputs as follows:

- a. Rainfall from USWB TP40
 - (1) 24 hour, probable maximum precipitation rainfall
 - (2) 24 hour, Assumption A rainfall
 - (3) 24 hour, 300 year rainfall (extrapolated)
- b. Drainage area = 56.4 square miles.
- c. Time of concentration = 9.5 hours.
- d. Antecedent moisture condition = II.
- e. Soil Type CN = 80.

2. Spillway release rates were based on the broad-crested weir equation:

$$Q = CLH^{\frac{3}{2}} \quad (C = 3.7, L = 817 \text{ feet}), \text{ where } H \text{ is the head on the weir crest.}$$

3. Floods were routed through the spillway and outlet channel to determine the capacity of the spillway discharge system. Outflow hydrographs (assuming free discharge from the spillway) are shown on Plate 16.

4. Correlation of flood routing and spillway outlet channel is shown on Plate 17.

